

### 9.3.2.Performance criterion : B

	Criterion B
Output characteristics	Voltage permitted to vary within the inverse time characteristics applicable (<100 m sec limits in Figures 1, 2 or 3 of IEC 62040-3)
External and internal indications and metering	Change only during test
Control signals to external devices	Change only temporarily in consistency with the actual Uninterruptible power systems mode of operation
Mode of operation	Change only temporarily

## 9.4. EUT Configuration

The configuration of EUT are listed in Section 4.3.

## 9.5. Operating Condition of EUT

Same as conducted emission measurement, which is listed in Section 4.4. except the test set up replaced by Section 9.1.

## 9.6. Test Procedure

### 9.6.1.Air Discharge:

This test is done on a non-conductive surface. The round discharge tip of the discharge electrode shall be approached as fast as possible to touch the EUT. After each discharge, the discharge electrode shall be removed from the EUT. The generator is then re-triggered for a new single discharge and repeated 10 times for each pre-selected test point. This procedure shall be repeated until all the air discharge completed

### 9.6.2.Contact Discharge:

All the procedure shall be same as Section 9.6.1. except that the tip of the discharge electrode shall touch the EUT before the discharge switch is operated.

### 9.6.3.Indirect discharge for horizontal coupling plane

At least 10 single discharges(in the most sensitive polarity) shall be applied at the front edge of each HCP opposite the center point of each unit(if applicable) of the EUT and 0.1m from the front of the EUT. The long axis of the discharge electrode shall be in the plane of the HCP and perpendicular to its front edge during the discharge.

### 9.6.4.Indirect discharge for vertical coupling plane

At least 10 single discharge (in the most sensitive polarity) shall be applied to the center of one vertical edge of the coupling plane. The coupling plane, of dimensions 0.5m X 0.5m, is placed parallel to, and positioned at a distance of 0.1m from the EUT. Discharges shall be applied to the coupling plane, with this plane in sufficient different positions that the four faces of the EUT are completely illuminated.

## 9.7. Test Results

PASS

Please refer to the following page.

## Electrostatic Discharge Test Result

SHENZHEN EMTEK CO., LTD

Applicant : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD. <hr/> EUT : Uninterruptible power systems <hr/> M/N : YDC3320H <hr/> Power Supply : AC 380V/50Hz <hr/> Test Mode : Line mode, Bat mode <hr/> Test Engineer : YU	Test Date : January 16, 2014 <hr/> Temperature : 22°C <hr/> Humidity : 50% <hr/> Actual Criterion : B <hr/> Air discharge : ±8kV <hr/> Contact discharge : ±4kV	
Location	Kind A-Air Discharge C-Contact Discharge	Result
Screen	A	A
Button	A	A
Slot	A	A
Metal	C	A
Screw	C	A
HCP	C	A
VCP of front	C	A
VCP of rear	C	A
VCP of left	C	A
VCP of right	C	A
Test Equipment: ESD Simulator (TESEQAG, NSG 437)		

## Electrostatic Discharge Test Result

SHENZHEN EMTEK CO., LTD

Applicant : SHENZHEN KSTAR SCIENCE & TECHNOLOGY CO., LTD. <hr/> EUT : Uninterruptible power systems <hr/> M/N : YDC3340H <hr/> Power Supply : AC 380V/50Hz <hr/> Test Mode : Line mode, Bat mode <hr/> Test Engineer : KY	Test Date : September 05, 2014 <hr/> Temperature : 22°C <hr/> Humidity : 50% <hr/> Actual Criterion : B <hr/> Air discharge : ±8kV <hr/> Contact discharge : ±4kV	
Location	Kind A-Air Discharge C-Contact Discharge	Result
Screen	A	A
Button	A	A
Port	C	A
Metal	C	A
Screw	C	A
HCP	C	A
VCP of front	C	A
VCP of rear	C	A
VCP of left	C	A
VCP of right	C	A
Test Equipment: ESD Simulator (TESEQAG, NSG 437)		

## 10. RF FIELD STRENGTH SUSCEPTIBILITY TEST


### 10.1. Block Diagram of Test

#### 10.1.1. Block diagram of connection between the EUT and Load



(EUT: Uninterruptible power systems)

#### 10.1.2. Block diagram of RS test setup



(EUT: Uninterruptible power systems)

### 10.2. Test Standard

IEC 61000-4-3:2006+A1:2007+A2:2010 (level 3: 10V / m)

### 10.3. Severity Levels and Performance Criterion

#### 10.3.1. Severity Levels

Level	Field Strength V/m
-------	--------------------

1.	1
2.	3
3.	10
X	Special

10.3.2. Performance Criterion : A

	<b>Criterion A</b>
External and internal indications and metering (LCD)	No change
Output characteristics (Load)	No change
Control signals to external devices (Signal line)	No change
Mode of operation	No change

10.4.EUT Configuration on Test

The configuration of the EUT is same as Section 4.3.

10.5.Operating Condition of EUT

Same as radiated emission measurement which is listed in Section 4.4, except the test setup replaced as Section 10.1.

10.6.Test Procedure

The EUT is placed on a table which is 0.1m high above the ground. The EUT is set 3 meters away from the transmitting antenna which is mounted on an antenna tower. Both horizontal and vertical polarization of the antenna are set on test. Each of the four sides of the EUT must be faced this transmitting antenna and measured individually.

In order to judge the EUT performance, a CCD camera is used to monitor its screen. All the scanning conditions are as following:

Condition of Test	Remark
-----	-----
1. Fielded Strength	10V/m
2. Radiated Signal	Modulated
3. Scanning Frequency	80-1000MHz
4. Sweep time of radiated	0.0015 Decade/s
5. Dwell Time	1 Sec.

10.7.Test Results

**PASS.**

Please refer to the following page.



SHENZHEN EMTEK CO., LTD.

Applicant : SHENZHEN KSTAR SCIENCE & TECHNOLOGY CO., LTD. <hr/> EUT : Uninterruptible power systems <hr/> M/N : YDC3340H <hr/> Field Strength : 10V/m <hr/> Power Supply : AC 380V/50Hz <hr/> Test Engineer : KY <hr/>	Test Date : September 05, 2014 <hr/> Temperature : 22°C <hr/> Humidity : 50% <hr/> Actual Criterion : A <hr/> Test Mode : Line mode, Bat mode <hr/> Frequency Range : 80 to 1000 MHz <hr/>	
Modulation: <input type="checkbox"/> None <input type="checkbox"/> Pulse <input checked="" type="checkbox"/> AM 1KHz 80%		
Frequency Rang 1: 80~ 1000MHz Frequency Rang 2: N/A		
Steps	# / %	# / %
	Horizontal      Vertical	Horizontal      Vertical
Front	A                      A	
Right	A                      A	
Rear	A                      A	
Left	A                      A	
Test Equipment : 1. Signal Generator: N5181A (Agilent) 2. Power Amplifier: 80RF1000-175 (MILMEGA) & AS1860-50 (MILMEGA) 3. Log.-Per. Antenna: VULP 9118E (SCHWARZBECK) 4. RF Power Meter. Dual Channel: 4232A (BOONTON) 5. Field Strength Meter: RSS1006A (DARE)		
Note: /		

## 11. ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST


### 11.1. Block Diagram of Test Setup

#### 11.1.1. Block Diagram of the EUT



(EUT: Uninterruptible power systems)

#### 11.1.2. EFT Test Setup



(EUT: Uninterruptible power systems)

### 11.2. Test Standard

IEC 61000-4-4:2012 (Level 3: 2kV/5kHz for AC mains)

### 11.3. Severity Levels and Performance Criterion

#### 11.3.1. Severity level

Level	Open Circuit Output Test Voltage $\pm 10\%$	
	On Power Supply Lines	On I/O (Input/Output) Signal data and control lines
1.	0.5 kV	0.25 kV
2.	1 kV	0.5 kV
3.	2 kV	1 kV
4.	4 kV	2 kV
X	Special	Special

### 11.3.2.Performance criterion : B

	Criterion B
Output characteristics	Voltage permitted to vary within the inverse time characteristics applicable (<100 m sec limits in Figures 1, 2 or 3 of IEC 62040-3)
External and internal indications and metering	Change only during test
Control signals to external devices	Change only temporarily in consistency with the actual Uninterruptible power systems mode of operation
Mode of operation	Change only temporarily

### 11.4.EUT Configuration

The configuration of EUT is listed in Section 4.4.

### 11.5.Operating Condition of EUT

11.5.1.Setup the EUT as shown in Section 11.1.

11.5.2.Turn on the power of all equipments.

11.5.3.Let the EUT work in test mode (Line mode) and measure it.

### 11.6.Test Procedure

The EUT is put on the table which is 0.1m high above the ground. This reference ground plane shall project beyond the EUT by at least 0.1m on all sides and the minimum distance between EUT and all other conductive structure, except the ground plane beneath the EUT, shall be more than 0.5m.

11.6.1. For input and output AC power ports:

The EUT is connected to the power mains by using a coupling device which couples the EFT interference signal to AC power lines. Both polarities of the test voltage should be applied during compliance test and the duration of the test is 2 mins.

11.6.2. For signal line and control lines ports:

It's unnecessary to test.

11.6.3. For DC output line ports:

It's unnecessary to test.

### 11.7.Test Result

**PASS.**

Please refer to the following page.

## Electrical Fast Transient/Burst Test Results

SHENZHEN EMTEK CO., LTD.

Standard	IEC 61000-4-4	Result: <input checked="" type="checkbox"/> PASS / <input type="checkbox"/> FAIL	
Applicant : <u>SHENZHEN KSTAR SCIENCE &amp; TECHNOLOGY CO., LTD.</u> EUT : <u>Uninterruptible power systems</u> M/N : <u>YDC3340H</u> Input Voltage : <u>AC 380V/50Hz</u> Actual Criterion : <u>B</u> Ambient Condition : <u>23 °C</u> <span style="float: right;"><u>55% RH</u></span>			
Operation Mode: Line mode			
Line : <input checked="" type="checkbox"/> AC input power ports and AC output power ports		Line : <input type="checkbox"/> Signal <input type="checkbox"/> I/O Cable	
Coupling : <input checked="" type="checkbox"/> Direct		Coupling : <input type="checkbox"/> Capacitive	
Test Time : 120s			
Line	Test Voltage	Result(+)	Result(-)
AC input power ports: L1, L2, L3, N, PE	2kV	A	A
L1-L2, L1-L3, L2-L3, L1-N, L2-N, L3-N	2kV	A	A
L1-PE, L2-PE, L3-PE, N-PE	2kV	A	A
L1-L2-PE, L1-L3-PE, L2-L3-PE, L1-L2-L3, L1-L2-N, L1-L3-N, L2-L3-N, L1-N-PE, L2-N-PE, L3-N-PE	2kV	A	A
L1-L2-L3-PE, L1-L2-L3-N, L1-L2-N-PE, L1-L3-N-PE, L2-L3-N-PE	2kV	A	A
AC output power ports: L1, L2, L3, N, PE	2kV	A	A
L1-L2, L1-L3, L2-L3, L1-N, L2-N, L3-N	2kV	A	A
L1-PE, L2-PE, L3-PE, N-PE	2kV	A	A
L1-L2-PE, L1-L3-PE, L2-L3-PE, L1-L2-L3, L1-L2-N, L1-L3-N, L2-L3-N, L1-N-PE, L2-N-PE, L3-N-PE	2kV	A	A
L1-L2-L3-PE, L1-L2-L3-N, L1-L2-N-PE, L1-L3-N-PE, L2-L3-N-PE	2kV	A	A
Note: /			
Test Equipment		Burst Tester Model : PEFT 40100, CDN 163	

## Electrical Fast Transient/Burst Test Results

SHENZHEN EMTEK CO., LTD.

Standard	IEC 61000-4-4	Result: <input checked="" type="checkbox"/> PASS / <input type="checkbox"/> FAIL	
Applicant : <u>SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.</u>			
EUT : <u>Uninterruptible power systems</u>			
M/N : <u>YDC3320S/H</u>			
Input Voltage : <u>AC 380V/50Hz</u>			
Actual Criterion : <u>B</u>			
Ambient Condition : <u>23 °C</u> <span style="float: right;"><u>55% RH</u></span>			
Operation Mode: Line mode			
Line : <input checked="" type="checkbox"/> AC input power ports and AC output power ports		Line : <input type="checkbox"/> Signal <input type="checkbox"/> I/O Cable	
Coupling : <input checked="" type="checkbox"/> Direct		Coupling : <input type="checkbox"/> Capacitive	
Test Time : 120s			
Line	Test Voltage	Result(+)	Result(-)
AC input power ports: L1, L2, L3, N, PE	2kV	A	A
L1-L2, L1-L3, L2-L3, L1-N, L2-N, L3-N	2kV	A	A
L1-PE, L2-PE, L3-PE, N-PE	2kV	A	A
L1-L2-PE, L1-L3-PE, L2-L3-PE, L1-L2-L3, L1-L2-N, L1-L3-N, L2-L3-N, L1-N-PE, L2-N-PE, L3-N-PE	2kV	A	A
L1-L2-L3-PE, L1-L2-L3-N, L1-L2-N-PE, L1-L3-N-PE, L2-L3-N-PE	2kV	A	A
AC output power ports: L1, L2, L3, N, PE	2kV	A	A
L1-L2, L1-L3, L2-L3, L1-N, L2-N, L3-N	2kV	A	A
L1-PE, L2-PE, L3-PE, N-PE	2kV	A	A
L1-L2-PE, L1-L3-PE, L2-L3-PE, L1-L2-L3, L1-L2-N, L1-L3-N, L2-L3-N, L1-N-PE, L2-N-PE, L3-N-PE	2kV	A	A
L1-L2-L3-PE, L1-L2-L3-N, L1-L2-N-PE, L1-L3-N-PE, L2-L3-N-PE	2kV	A	A
Note: /			
Test Equipment		Burst Tester Model : PEFT 40100, CDN 163	

## 12. SURGE IMMUNITY TEST


### 12.1. Block Diagram of Test Setup

#### 12.1.1. Block Diagram of the EUT



(EUT: Uninterruptible power systems)

#### 12.1.2. Surge Test Setup



(EUT: Uninterruptible power systems)

### 12.2. Test Standard

IEC 61000-4-5:2014 (Line to Line: Level 2, 1.0kV, Line to earth: Level 3, 2.0kV)

### 12.3. Severity Levels and Performance Criterion

#### 12.3.1. Severity level

Severity Level	Open-Circuit Test Voltage kV
1	0.5
2	1.0
3	2.0
4	4.0
*	Special

#### 12.3.2. Performance criterion: B

	Criterion B
Output characteristics	Voltage permitted to vary within the inverse time characteristics applicable (<100 m sec limits in Figures 1, 2 or 3 of IEC 62040-3)
External and internal indications and metering	Change only during test
Control signals to external devices	Change only temporarily in consistency with the actual Uninterruptible power systems mode of operation
Mode of operation	Change only temporarily

## 12.4.EUT Configuration

The configuration of EUT is listed in Section 4.3.

## 12.5.Operating Condition of EUT

12.5.1.Setup the EUT as shown in Section 12.1.

12.5.2.Turn on the power of all equipments.

12.5.3.Let the EUT work in test mode (Line mode) and measure it.

## 12.6.Test Procedure

- 1) Set up the EUT and test generator as shown on Section 12.1.2.  
For line to line coupling mode, provide 1kV 1.2/50us voltage surge.  
For line to earth mode, provide 2kV 1.2/50us voltage surge.  
(At open-circuit condition) and 8/20us current surge to EUT selected points.
- 2) At least 5 positive and 5 negative (polarity) tests with a maximum 1/min repetition rate are conducted during test.
- 3) Different phase angles are done individually.
- 4) Record the EUT operating situation during compliance test and decide the EUT immunity criterion for above each test.

## 12.7.Test Result

**PASS.**

Please refer to the following page.





## 13. INJECTED CURRENTS SUSCEPTIBILITY TEST


### 13.1. Block Diagram of Test Setup

#### 13.1.1. Block Diagram of the EUT



(EUT: Uninterruptible power systems)

#### 13.1.2. Block Diagram of Test Setup



### 13.2. Test Standard

IEC 61000-4-6:2008 (Level 3: 10V (rms) (0.15MHz ~ 80MHz))

### 13.3. Severity Levels and Performance Criterion

#### 13.3.1. Severity level

Level	Field Strength V
1	1
2	3
3	10
X	Special

#### 13.3.2. Performance criterion: A

	Criterion A
External and internal indications and metering (LCD)	No change
Output characteristics (Load)	No change
Control signals to external devices (Signal line)	No change
Mode of operation	No change

### 13.4.EUT Configuration

The configuration of EUT is listed in Section 4.3.

### 13.5.Operating Condition of EUT

13.5.1.Setup the EUT as shown in Section 13.1.

13.5.2.Turn on the power of all equipments.

13.5.3.Let the EUT work in test mode (Line mode) and measure it.

### 13.6.Test Procedure

- 1) Set up the EUT, CDN and test generators as shown on Section 13.1.2.
- 2) Let the EUT work in test mode and measure it.
- 3) The EUT are placed on an insulating support 0.1m high above a ground reference plane. CDN (coupling and decoupling device) is placed on the ground plane about 0.3m from EUT. Cables between CDN and EUT are as short as possible, and their height above the ground reference plane shall be between 30 and 50 mm (where possible).
- 4) The disturbance signal described below is injected to EUT through CDN.
- 5) The EUT operates within its operational mode(s) under intended climatic conditions after power on.
- 6) The frequency range is swept from 150KHz to 80MHz using 10V signal level, and with the disturbance signal 80% amplitude modulated with a 1KHz sine wave.
- 7) The rate of sweep shall not exceed  $1.5 \cdot 10^{-3}$  decades/s. Where the frequency is swept incrementally, the step size shall not exceed 1% of the start and thereafter 1% of the preceding frequency value.
- 8) Recording the EUT operating situation during compliance testing and decide the EUT immunity criterion.

### 13.7.Test Results

**PASS.**

Please refer to the following page.

## Injected Currents Susceptibility Test Results

SHENZHEN EMTEK CO., LTD.

Applicant : <u>SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.</u> EUT : <u>Uninterruptible power systems</u> M/N : <u>YDC3320S/H</u> Power Supply : <u>AC 380V/50Hz</u> Test Engineer : <u>YU</u>	Test Date : <u>January 16, 2014</u> Temperature : <u>23°C</u> Humidity : <u>50%</u> Actual Criterion : <u>A</u>			
Test Mode : Line mode				
Frequency Range (MHz)	Injected Position	Strength (Unmodulated)	Criterion	Result
0.15 ~ 80	AC Input	10V	A	A
0.15 ~ 80	AC Output	10V	A	A
Remark : 1. Modulation Signal:1KHz 80% AM Measurement Equipment : Simulator: CWS 500 (SWITZERLAND EMTEST) CDN : <input type="checkbox"/> CDN-M2 (SWITZERLAND EMTEST) <input checked="" type="checkbox"/> CDN-M3 (SWITZERLAND EMTEST) <input type="checkbox"/> Injection Clamp (EMTEST F-2031-23MM)			Note: /	

## Injected Currents Susceptibility Test Results

SHENZHEN EMTEK CO., LTD.

Applicant : <u>SHENZHEN KSTAR SCIENCE &amp; TECHNOLOGY CO., LTD.</u> EUT : <u>Uninterruptible power systems</u> M/N : <u>YDC3340H</u> Power Supply : <u>AC 380V/50Hz</u> Test Engineer : <u>KY</u>		Test Date : <u>September 05, 2014</u> Temperature : <u>23°C</u> Humidity : <u>50%</u> Actual Criterion : <u>A</u>		
Test Mode : Line mode				
Frequency Range (MHz)	Injected Position	Strength (Unmodulated)	Criterion	Result
0.15 ~ 80	AC Input	10V	A	A
0.15 ~ 80	AC Output	10V	A	A
Remark : 1. Modulation Signal:1KHz 80% AM Measurement Equipment : Simulator: CIT-10 (FRANKONIA) CDN : <input type="checkbox"/> CDN-M2 (SWITZERLAND EMTEST) <input type="checkbox"/> CDN-M3 (SWITZERLAND EMTEST) <input type="checkbox"/> Injection Clamp (EMTEST F-2031-23MM) <input checked="" type="checkbox"/> CDN-M532S(Teseq)			Note: /	

## 14. MAGNETIC FIELD SUSCEPTIBILITY TEST


### 14.1. Block Diagram of Test

#### 14.1.1. Block diagram of test setup



(EUT: Uninterruptible power systems)

#### 14.1.2. Magnetic field test setup



(EUT: Uninterruptible power systems)

### 14.2. Test Standard

IEC 61000-4-8:2009, (Severity Level 4: 30A / m)

### 14.3. Severity Levels and Performance Criterion

#### 14.3.1. Severity Levels

Level	Field Strength A/m
1	1
2	3
3	10
4	30
5	100
X	Special

#### 14.3.2.Performance Criterion: A

	Criterion A
Output characteristics	Voltage permitted to vary within the inverse time characteristics applicable (<100 m sec limits in Figures 1, 2 or 3 of IEC 62040-3)
External and internal indications and metering	Change only during test
Control signals to external devices	Change only temporarily in consistency with the actual Uninterruptible power systems mode of operation
Mode of operation	Change only temporarily

#### 14.4.EUT Configuration on Test

The configuration of the EUT is same as Section 4.3.

#### 14.5.Test Procedure

The EUT is placed in the middle of a induction coil (1\*1m), under which is a 1\*1\*0.1m (high) table, this small table is also placed on a larger table, 0.1 m above the ground. Both horizontal and vertical polarization of the induction coil is set on test, so that each side of the EUT is affected by the magnetic field. Also can reach the same aim by change the position of the EUT.

#### 14.6.Test Results

**PASS.**

Please refer to the following page.

## Magnetic Field Immunity Test Result

SHENZHEN EMTEK CO., LTD.

Standard	IEC 61000-4-8			Result: <input checked="" type="checkbox"/> Pass / <input type="checkbox"/> Fail
Applicant : SHENZHEN KSTAR SCIENCE & TECHNOLOGY CO., LTD.				
EUT	Uninterruptible power systems		M/N	YDC3340H
Input Voltage	AC 380V/50Hz			
Date of Test	September 05, 2014		Test Engineer	KY
Ambient Condition	Temp	22°C	Humid	50%
Actual Criterion : A				
Operation Mode : Line mode, Bat mode				
Test Level (A/M)	Testing Duration	Coil Orientation	Criterion	Result
30	5 mins	X	A	A
30	5 mins	Y	A	A
30	5 mins	Z	A	A
Operation Mode : N/A				
Test Level (A/M)	Testing Duration	Coil Orientation	Criterion	Result
Test Equipment	Magnetic Field Test : HEAFELY MAG 100.1			
Note: /				

## Magnetic Field Immunity Test Result

SHENZHEN EMTEK CO., LTD.

Standard	IEC 61000-4-8			Result: <input checked="" type="checkbox"/> Pass / <input type="checkbox"/> Fail
<p>Applicant : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.</p> <p>EUT : Uninterruptible power systems M/N : YDC3320S/H</p> <p>Input Voltage : AC 380V/50Hz</p> <p>Date of Test : January 16, 2014 Test Engineer : YU</p> <p>Ambient Condition : Temp : 22°C Humid : 50%</p> <p>Actual Criterion : A</p>				
Operation Mode : Line mode, Bat mode				
Test Level (A/M)	Testing Duration	Coil Orientation	Criterion	Result
30	5 mins	X	A	A
30	5 mins	Y	A	A
30	5 mins	Z	A	A
Operation Mode : N/A				
Test Level (A/M)	Testing Duration	Coil Orientation	Criterion	Result
Test Equipment	Magnetic Field Test : HEAFELY MAG 100.1			
Note: /				

## 15. VOLTAGE DIPS AND INTERRUPTIONS TEST


### 15.1. Block Diagram of Test Setup

#### 15.1.1. Block Diagram of the EUT



(EUT: Uninterruptible power systems)

#### 15.1.2. Dips Test Setup



(EUT: Uninterruptible power systems)

### 15.2. Test Standard

IEC 61000-4-11:2004

### 15.3. Severity Levels and Performance Criterion

#### 15.3.1. Severity level

Test Level %UT	Voltage dip and short interruptions %UT	Duration (in period)
0	100	0.5
40	60	1
70	30	5
		10
		25
		50
		*

15.3.2.Performance criterion: B

	Criterion B
Output characteristics	Voltage permitted to vary within the inverse time characteristics applicable (<100 m sec limits in Figures 1, 2 or 3 of IEC 62040-3)
External and internal indications and metering	Change only during test
Control signals to external devices	Change only temporarily in consistency with the actual Uninterruptible power systems mode of operation
Mode of operation	Change only temporarily

15.4.EUT Configuration

The configuration of EUT is listed in Section 4.3.

15.5.Operating Condition of EUT

15.5.1.Setup the EUT as shown in Section 15.1.

15.5.2.Turn on the power of all equipments.

15.5.3.Let the EUT work in test mode (Line mode) and measure it.

15.6.Test Procedure

- 1) Set up the EUT and test generator as shown on Section 15.1.2.
- 2) The interruption is introduced at selected phase angles with specified duration.
- 3) Record any degradation of performance.

15.7.Test Result

**PASS.**

Please refer to the following page.

## Voltage Dips And Interruptions Test Results

SHENZHEN EMTEK CO., LTD.

Applicant : <u>SHENZHEN KSTAR SCIENCE &amp; TECHNOLOGY CO., LTD.</u>		Test Date : <u>September 05, 2014</u>		
EUT : <u>Uninterruptible power systems</u>		Temperature : <u>22°C</u>		
M/N : <u>YDC3340H</u>		Humidity : <u>50%</u>		
Power Supply : <u>AC 380V/50Hz</u>		Test Engineer : <u>KY</u>		
Test Mode: Line mode				
Test Level % U <sub>T</sub>	Voltage Dips & Short Interruptions % U <sub>T</sub>	Duration (in periods)	Criterion <input type="checkbox"/> A <input checked="" type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D	Result
0	100	0.5P	B	A
40	60	10P	B	A
70	30	25P	B	A
0	100	250P	B	B
Note: Test in 0%, 250P, light appears flicker, but can self-recovery.				

## Voltage Dips And Interruptions Test Results


SHENZHEN EMTEK CO., LTD.

Applicant : <u>SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.</u>		Test Date : <u>January 16, 2014</u>		
EUT : <u>Uninterruptible power systems</u>		Temperature : <u>22°C</u>		
M/N : <u>YDC3320S/H</u>		Humidity : <u>50%</u>		
Power Supply : <u>AC 380V/50Hz</u>		Test Engineer : <u>YU</u>		
Test Mode: Line mode				
Test Level % U <sub>T</sub>	Voltage Dips & Short Interruptions % U <sub>T</sub>	Duration (in periods)	Criterion <input type="checkbox"/> A <input checked="" type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D	Result
0	100	0.5P	B	A
40	60	10P	B	A
70	30	25P	B	A
0	100	250P	B	B
Note: Test in 0%, 250P, light appears flicker, but can self-recovery.				

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Vertical
Tester: CSL	Model: YDC3340H	Mode: FULL LOAD
Test Time:2014/8/22 13:34	Temperature:20	Humidity:53
Power:AC 380V/50Hz	Test Distance:10M	EUT:Uninterruptible Power supply
Note:BAT MODE		

## 2. Chart




## 3. Result

No	Frequency	QP	Correct factor	Reading level	Limit1	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB (uV/m)	dB	dB(uV)	dB(uV/m)	dB	Degree	cm	
1	36.78	31.6	-31.47	63.07	40	-8.4			Pass
2	56.14	30.2	-30.01	60.21	40	-9.8			Pass
3	73.56	31.4	-34.68	66.08	40	-8.6			Pass
4	114.22	35.2	-31.25	66.45	40	-4.8			Pass
5	145.20	34.9	-34.37	69.27	40	-5.1			Pass
6	176.18	31.2	-32.42	63.62	40	-8.8			Pass

## 6. HARMONIC CURRENT EMISSION MEASUREMENT

### 6.1. Block Diagram of Test Setup



(EUT: Uninterruptible power systems)

### 6.2. Measuring Standard

EN 61000-3-12: 2011 CLASS A

### 6.3. Operation Condition of EUT

Same as Section 4.4, except the test setup replaced as Section 6.1.

### 6.4. Measuring Results

**PASS.**

Please see the attached pages.



**Current Test Result Summary (Phase A-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 I-THD(%): 2.529 Limit(%): 13.000 PWHD(%): 4.603 PWHD Limit(%): 22.000

**Highest parameter values during test:**

V_RMS (Volts): 229.50	Frequency(Hz): 50.00
I_Peak (Amps): 35.031	I_RMS (Amps): 23.382
I <sub>1</sub> -Ref (Amps): 18.354	Crest Factor: 1.701
Power (Watts): 5326	Power Factor: 0.995

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.026	1.453	1.8	0.032	2.180	1.47	Pass
3	0.342	N/A	N/A	0.355	N/A	N/A	N/A
4	0.013	0.727	1.8	0.016	1.090	1.49	Pass
5	0.193	1.944	9.9	0.196	2.916	6.72	Pass
6	0.004	0.484	0.9	0.005	0.727	0.76	Pass
7	0.067	1.308	5.1	0.072	1.962	3.65	Pass
8	0.004	0.363	1.2	0.007	0.545	1.27	Pass
9	0.131	N/A	N/A	0.134	N/A	N/A	N/A
10	0.003	0.291	1.0	0.004	0.436	1.02	Pass
11	0.059	0.563	10.4	0.066	0.845	7.77	Pass
12	0.003	0.242	1.4	0.005	0.363	1.34	Pass
13	0.068	0.363	18.6	0.073	0.545	13.31	Pass
14	0.003	N/A	N/A	0.006	N/A	N/A	N/A
15	0.055	N/A	N/A	0.059	N/A	N/A	N/A
16	0.003	N/A	N/A	0.006	N/A	N/A	N/A
17	0.048	N/A	N/A	0.052	N/A	N/A	N/A
18	0.003	N/A	N/A	0.004	N/A	N/A	N/A
19	0.044	N/A	N/A	0.049	N/A	N/A	N/A
20	0.004	N/A	N/A	0.005	N/A	N/A	N/A
21	0.044	N/A	N/A	0.049	N/A	N/A	N/A
22	0.004	N/A	N/A	0.005	N/A	N/A	N/A
23	0.043	N/A	N/A	0.048	N/A	N/A	N/A
24	0.004	N/A	N/A	0.005	N/A	N/A	N/A
25	0.043	N/A	N/A	0.048	N/A	N/A	N/A
26	0.003	N/A	N/A	0.007	N/A	N/A	N/A
27	0.045	N/A	N/A	0.050	N/A	N/A	N/A
28	0.003	N/A	N/A	0.005	N/A	N/A	N/A
29	0.048	N/A	N/A	0.052	N/A	N/A	N/A
30	0.003	N/A	N/A	0.004	N/A	N/A	N/A
31	0.045	N/A	N/A	0.049	N/A	N/A	N/A
32	0.004	N/A	N/A	0.005	N/A	N/A	N/A
33	0.043	N/A	N/A	0.047	N/A	N/A	N/A
34	0.003	N/A	N/A	0.005	N/A	N/A	N/A
35	0.045	N/A	N/A	0.048	N/A	N/A	N/A
36	0.003	N/A	N/A	0.004	N/A	N/A	N/A
37	0.044	N/A	N/A	0.046	N/A	N/A	N/A
38	0.003	N/A	N/A	0.005	N/A	N/A	N/A
39	0.036	N/A	N/A	0.037	N/A	N/A	N/A
40	0.010	N/A	N/A	0.015	N/A	N/A	N/A

*Note: Measured reference fundamental current limits were applied for this test.*

**Voltage Source Verification Data (Phase A-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 Measured source distortion is within the requirements of the standards  
 Measurements are compliant with IEC/EN61000-3-12(2004:11) & IEC/EN61000-4-7

Highest parameter values during test:

Voltage (Vrms): 229.50	Frequency(Hz): 50.00
I_Peak (Amps): 35.031	I_RMS (Amps): 23.382
I <sub>1</sub> -Ref (Amps): 18.354	Crest Factor: 1.701
Power (Watts): 5326	Power Factor: 0.995


Harm#	Harmonics V-rms	Limit V-rms	% of Limit	Status
2	0.316	0.918	34.45	OK
3	0.164	2.868	5.72	OK
4	0.027	0.918	2.95	OK
5	0.120	3.440	3.49	OK
6	0.007	0.918	0.74	OK
7	0.118	2.868	4.10	OK
8	0.013	0.918	1.38	OK
9	0.184	1.376	13.39	OK
10	0.011	0.918	1.22	OK
11	0.118	1.605	7.37	OK
12	0.013	0.688	1.83	OK
13	0.126	1.376	9.13	OK
14	0.012	0.688	1.78	OK
15	0.107	0.688	15.62	OK
16	0.014	0.688	1.98	OK
17	0.088	0.688	12.82	OK
18	0.017	0.688	2.45	OK
19	0.073	0.688	10.60	OK
20	0.023	0.688	3.33	OK
21	0.076	0.688	11.09	OK
22	0.014	0.688	1.99	OK
23	0.085	0.688	12.36	OK
24	0.015	0.688	2.17	OK
25	0.098	0.688	14.19	OK
26	0.015	0.688	2.16	OK
27	0.116	0.688	16.79	OK
28	0.013	0.688	1.90	OK
29	0.118	0.688	17.14	OK
30	0.015	0.688	2.20	OK
31	0.108	0.688	15.66	OK
32	0.017	0.688	2.46	OK
33	0.117	0.688	17.01	OK
34	0.015	0.688	2.19	OK
35	0.114	0.688	16.57	OK
36	0.016	0.688	2.27	OK
37	0.114	0.688	16.60	OK
38	0.017	0.688	2.43	OK
39	0.099	0.688	14.34	OK
40	0.024	0.688	3.43	OK

**Harmonics – Per EN/IEC61000-3-12(Phase B-Run time)**

EUT: UPS(YDC3320H)	Tested by: YU
Test category: Stage:2 1ph & B3ph(Rsce=33)	Test Margin: 100
Test date: 2014-1-14	Start time: PM 01:30:04
Test duration (min): 2.5	End time: PM 01:32:56
Comment: FULL LOAD	Data file name: WIN2106_H-000010.cts_data
Customer: KSTAR	


Test Result: Pass                      Source qualification: Normal

Current & voltage waveforms



Harmonics and Class 2 limit line

European Limits



**Test result: Pass                      Worst harmonic was #13 with 12.60 % of the limit.**

**Current Test Result Summary (Phase B-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 I-THD(%): 2.267 Limit(%): 13.000 PWHD(%): 3.866 PWHD Limit(%): 22.000

**Highest parameter values during test:**

V_RMS (Volts):	229.55	Frequency(Hz):	50.00
I_Peak (Amps):	33.975	I_RMS (Amps):	22.667
I <sub>1</sub> -Ref (Amps):	18.086	Crest Factor:	1.672
Power (Watts):	5175	Power Factor:	0.997

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.011	1.434	0.8	0.016	2.151	0.73	Pass
3	0.342	N/A	N/A	0.348	N/A	N/A	N/A
4	0.009	0.717	1.2	0.011	1.076	1.02	Pass
5	0.117	1.918	6.1	0.120	2.878	4.17	Pass
6	0.004	0.478	0.9	0.006	0.717	0.78	Pass
7	0.078	1.291	6.0	0.081	1.936	4.16	Pass
8	0.004	0.359	1.1	0.006	0.538	1.03	Pass
9	0.131	N/A	N/A	0.103	N/A	N/A	N/A
10	0.003	0.287	0.9	0.004	0.430	0.82	Pass
11	0.031	0.556	5.5	0.036	0.834	4.26	Pass
12	0.002	0.239	0.9	0.003	0.359	0.96	Pass
13	0.045	0.359	12.6	0.050	0.538	9.30	Pass
14	0.003	N/A	N/A	0.004	N/A	N/A	N/A
15	0.036	N/A	N/A	0.040	N/A	N/A	N/A
16	0.003	N/A	N/A	0.004	N/A	N/A	N/A
17	0.037	N/A	N/A	0.043	N/A	N/A	N/A
18	0.003	N/A	N/A	0.004	N/A	N/A	N/A
19	0.037	N/A	N/A	0.042	N/A	N/A	N/A
20	0.003	N/A	N/A	0.003	N/A	N/A	N/A
21	0.035	N/A	N/A	0.041	N/A	N/A	N/A
22	0.002	N/A	N/A	0.003	N/A	N/A	N/A
23	0.035	N/A	N/A	0.039	N/A	N/A	N/A
24	0.004	N/A	N/A	0.005	N/A	N/A	N/A
25	0.037	N/A	N/A	0.041	N/A	N/A	N/A
26	0.004	N/A	N/A	0.010	N/A	N/A	N/A
27	0.038	N/A	N/A	0.041	N/A	N/A	N/A
28	0.003	N/A	N/A	0.004	N/A	N/A	N/A
29	0.039	N/A	N/A	0.043	N/A	N/A	N/A
30	0.003	N/A	N/A	0.005	N/A	N/A	N/A
31	0.042	N/A	N/A	0.045	N/A	N/A	N/A
32	0.004	N/A	N/A	0.006	N/A	N/A	N/A
33	0.037	N/A	N/A	0.039	N/A	N/A	N/A
34	0.004	N/A	N/A	0.005	N/A	N/A	N/A
35	0.040	N/A	N/A	0.042	N/A	N/A	N/A
36	0.003	N/A	N/A	0.005	N/A	N/A	N/A
37	0.036	N/A	N/A	0.038	N/A	N/A	N/A
38	0.004	N/A	N/A	0.006	N/A	N/A	N/A
39	0.028	N/A	N/A	0.029	N/A	N/A	N/A
40	0.008	N/A	N/A	0.012	N/A	N/A	N/A

Note: Measured reference fundamental current limits were applied for this test.

**Voltage Source Verification Data (Phase B-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 Measured source distortion is within the requirements of the standards  
 Measurements are compliant with IEC/EN61000-3-12(2004:11) & IEC/EN61000-4-7

Highest parameter values during test:

Voltage (Vrms): 229.55	Frequency(Hz): 50.00
I_Peak (Amps): 33.975	I_RMS (Amps): 22.667
I <sub>1</sub> -Ref (Amps): 18.086	Crest Factor: 1.672
Power (Watts): 5175	Power Factor: 0.997


Harm#	Harmonics V-rms	Limit V-rms	% of Limit	Status
2	0.306	0.918	33.36	OK
3	0.155	2.869	5.39	OK
4	0.027	0.918	2.92	OK
5	0.123	3.443	3.58	OK
6	0.013	0.918	1.46	OK
7	0.121	2.869	4.22	OK
8	0.018	0.918	1.93	OK
9	0.167	1.376	12.11	OK
10	0.010	0.918	1.12	OK
11	0.125	1.607	7.77	OK
12	0.015	0.688	2.21	OK
13	0.119	1.376	8.68	OK
14	0.016	0.688	2.33	OK
15	0.107	0.688	15.60	OK
16	0.018	0.689	2.56	OK
17	0.090	0.688	13.01	OK
18	0.015	0.688	2.11	OK
19	0.079	0.688	11.44	OK
20	0.012	0.688	1.79	OK
21	0.079	0.688	11.54	OK
22	0.013	0.689	1.83	OK
23	0.089	0.689	12.96	OK
24	0.019	0.689	2.72	OK
25	0.098	0.689	14.27	OK
26	0.017	0.688	2.43	OK
27	0.108	0.689	15.74	OK
28	0.014	0.688	2.02	OK
29	0.106	0.688	15.37	OK
30	0.017	0.688	2.41	OK
31	0.112	0.688	16.24	OK
32	0.020	0.688	2.85	OK
33	0.120	0.688	17.46	OK
34	0.017	0.688	2.50	OK
35	0.112	0.688	16.33	OK
36	0.014	0.689	2.09	OK
37	0.103	0.688	14.92	OK
38	0.015	0.689	2.21	OK
39	0.091	0.688	13.17	OK
40	0.019	0.689	2.76	OK

**Harmonics – Per EN/IEC61000-3-12(Phase C-Run time)**

EUT: UPS(YDC3320H)	Tested by: YU
Test category: Stage:2 1ph & B3ph(Rsce=33)	Test Margin: 100
Test date: 2014-1-14	Start time: PM 01:30:04
Test duration (min): 2.5	End time: PM 01:32:56
Comment: FULL LOAD	Data file name: WIN2106_H-000010.cts_data
Customer: KSTAR	


Test Result: Pass                      Source qualification: Normal

Current & voltage waveforms



Harmonics and Class 2 limit line

European Limits



**Test result: Pass                      Worst harmonic was #13 with 17.28 % of the limit.**

**Current Test Result Summary (Phase C-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 I-THD(%): 2.254 Limit(%): 13.000 PWHD(%): 4.258 PWHD Limit(%): 22.000

Highest parameter values during test:  
 V\_RMS (Volts): 229.50 Frequency(Hz): 50.00  
 I\_Peak (Amps): 35.707 I\_RMS (Amps): 23.775  
 I<sub>1</sub>-Ref (Amps): 18.785 Crest Factor: 1.656  
 Power (Watts): 5430 Power Factor: 0.997

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.021	1.489	1.4	0.026	2.234	1.18	Pass
3	0.342	N/A	N/A	0.307	N/A	N/A	N/A
4	0.010	0.745	1.3	0.012	1.117	1.12	Pass
5	0.190	1.992	9.5	0.193	2.987	6.47	Pass
6	0.007	0.496	1.5	0.009	0.745	1.15	Pass
7	0.060	1.340	4.5	0.065	2.010	3.24	Pass
8	0.005	0.372	1.4	0.007	0.558	1.20	Pass
9	0.131	N/A	N/A	0.141	N/A	N/A	N/A
10	0.004	0.298	1.2	0.005	0.447	1.11	Pass
11	0.049	0.577	8.6	0.054	0.866	6.24	Pass
12	0.004	0.248	1.6	0.006	0.372	1.54	Pass
13	0.062	0.372	16.8	0.068	0.558	12.25	Pass
14	0.004	N/A	N/A	0.006	N/A	N/A	N/A
15	0.050	N/A	N/A	0.053	N/A	N/A	N/A
16	0.004	N/A	N/A	0.007	N/A	N/A	N/A
17	0.045	N/A	N/A	0.049	N/A	N/A	N/A
18	0.004	N/A	N/A	0.005	N/A	N/A	N/A
19	0.044	N/A	N/A	0.048	N/A	N/A	N/A
20	0.004	N/A	N/A	0.005	N/A	N/A	N/A
21	0.038	N/A	N/A	0.042	N/A	N/A	N/A
22	0.004	N/A	N/A	0.006	N/A	N/A	N/A
23	0.036	N/A	N/A	0.041	N/A	N/A	N/A
24	0.004	N/A	N/A	0.006	N/A	N/A	N/A
25	0.037	N/A	N/A	0.043	N/A	N/A	N/A
26	0.004	N/A	N/A	0.009	N/A	N/A	N/A
27	0.037	N/A	N/A	0.043	N/A	N/A	N/A
28	0.004	N/A	N/A	0.006	N/A	N/A	N/A
29	0.041	N/A	N/A	0.046	N/A	N/A	N/A
30	0.004	N/A	N/A	0.006	N/A	N/A	N/A
31	0.043	N/A	N/A	0.047	N/A	N/A	N/A
32	0.004	N/A	N/A	0.007	N/A	N/A	N/A
33	0.045	N/A	N/A	0.049	N/A	N/A	N/A
34	0.004	N/A	N/A	0.006	N/A	N/A	N/A
35	0.045	N/A	N/A	0.047	N/A	N/A	N/A
36	0.003	N/A	N/A	0.005	N/A	N/A	N/A
37	0.043	N/A	N/A	0.047	N/A	N/A	N/A
38	0.004	N/A	N/A	0.005	N/A	N/A	N/A
39	0.041	N/A	N/A	0.043	N/A	N/A	N/A
40	0.009	N/A	N/A	0.014	N/A	N/A	N/A

Note: Measured reference fundamental current limits were applied for this test.

**Voltage Source Verification Data (Phase C-Run time)**

EUT: UPS(YDC3320H) Tested by: YU  
 Test category: Stage:2 1ph & B3ph(Rsce=33) Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:30:04 End time: PM 01:32:56  
 Test duration (min): 2.5 Data file name: WIN2106\_H-000010.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR

Test Result: Pass Source qualification: Normal  
 Measured source distortion is within the requirements of the standards  
 Measurements are compliant with IEC/EN61000-3-12(2004:11) & IEC/EN61000-4-7

Highest parameter values during test:

Voltage (Vrms): 229.50	Frequency(Hz): 50.00
I_Peak (Amps): 35.707	I_RMS (Amps): 23.775
I <sub>1</sub> -Ref (Amps): 18.785	Crest Factor: 1.656
Power (Watts): 5430	Power Factor: 0.997

Harm#	Harmonics V-rms	Limit V-rms	% of Limit	Status
2	0.272	0.918	29.62	OK
3	0.159	2.868	5.53	OK
4	0.032	0.918	3.47	OK
5	0.135	3.441	3.93	OK
6	0.008	0.918	0.92	OK
7	0.118	2.868	4.13	OK
8	0.016	0.918	1.77	OK
9	0.196	1.376	14.22	OK
10	0.013	0.918	1.42	OK
11	0.143	1.606	8.89	OK
12	0.014	0.688	2.10	OK
13	0.136	1.376	9.92	OK
14	0.016	0.688	2.38	OK
15	0.123	0.688	17.94	OK
16	0.016	0.688	2.30	OK
17	0.110	0.688	16.00	OK
18	0.018	0.688	2.57	OK
19	0.101	0.688	14.71	OK
20	0.019	0.688	2.71	OK
21	0.085	0.688	12.31	OK
22	0.015	0.688	2.15	OK
23	0.074	0.688	10.77	OK
24	0.020	0.688	2.85	OK
25	0.095	0.688	13.77	OK
26	0.021	0.688	3.03	OK
27	0.118	0.688	17.08	OK
28	0.014	0.688	2.10	OK
29	0.116	0.688	16.78	OK
30	0.019	0.688	2.74	OK
31	0.113	0.688	16.45	OK
32	0.021	0.688	2.99	OK
33	0.127	0.688	18.43	OK
34	0.021	0.688	3.00	OK
35	0.117	0.688	17.02	OK
36	0.014	0.688	2.05	OK
37	0.124	0.688	18.03	OK
38	0.017	0.688	2.41	OK
39	0.113	0.688	16.42	OK
40	0.024	0.688	3.44	OK

5th Harmonic Phase Angle and Magnitude for Phase A :

H-5\_min\_phase : -16.1 Degree (Lagging) H-5\_max\_phase : -28.9 Degree (Lagging)  
 H-5\_ave\_phase : 157.6 Degree (Leading)

H-5\_ave\_vector\_magnitude : 0.037 Amp H-5\_standard\_ave\_magnitude : 0.193 Amp  
 H-5\_standard\_max\_magnitude : 0.196 Amp


**Harmonics – Per EN/IEC61000-3-12(Phase A-Run time)**

EUT: Uninterruptible power systems  
 Test category: Stage:2 1ph & B3ph(Rsce=33)  
 Test date: 2014-9-5  
 Test duration (min): 2.5  
 Comment: Line Mode  
 Customer: KSTAR

Tested by: KY  
 Test Margin: 100  
 Start time: 01:30:04 PM  
 End time: 01:32:56 PM  
 Data file name: WIN2106\_H-000010.cts\_data


Test Result: Pass                      Source qualification: Normal

Current & voltage waveforms



Harmonics and Class 2 limit line

European Limits



**Test result: Pass                      Worst harmonic was #13 with 18.64 % of the limit.**






EUT: Uninterruptible power systems  
 Test category: Stage:2 1ph & B3ph(Rsce=33)  
 Test date: 2014-9-5  
 Test duration (min): 2.5  
 Comment: Line Mode  
 Customer: KSTAR

Tested by: KY  
 Test Margin: 100  
 Start time: 01:30:04 PM  
 End time: 01:32:56 PM  
 Data file name: WIN2106\_H-000010.cts\_data


Test Result: Pass Source qualification: Normal

Current & voltage waveforms



Harmonics and Class 2 limit line

European Limits



Test result: Pass Worst harmonic was #13 with 12.60 % of the limit.

**Current Test Result Summary (Phase B-Run time)**

EUT: Uninterruptible power systems  
 Test category: Stage:2 1ph & B3ph(Rsce=33)  
 Test date: 2014-9-5  
 Test duration (min): 2.5  
 Comment: Line Mode  
 Customer: KSTAR

Tested by: KY  
 Test Margin: 100  
 Start time: 01:30:04 PM  
 End time: 01:32:56 PM  
 Data file name: WIN2106\_H-000010.cts\_data

Test Result: Pass  
 I-THD(%): 2.267

Source qualification: Normal  
 Limit(%): 13.000  
 PWHD(%): 3.866  
 PWHD Limit(%): 22.000

Highest parameter values during test:

V_RMS (Volts):	229.50	Frequency(Hz):	50.00
I_Peak (Amps):	41.031	I_RMS (Amps):	34.382
I <sub>1</sub> -Ref (Amps):	31.354	Crest Factor:	1.672
Power (Watts):	8463	Power Factor:	0.995

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.011	1.434	0.8	0.016	2.151	0.73	Pass
3	0.342	N/A	N/A	0.348	N/A	N/A	N/A
4	0.009	0.717	1.2	0.011	1.076	1.02	Pass
5	0.117	1.918	6.1	0.120	2.878	4.17	Pass
6	0.004	0.478	0.9	0.006	0.717	0.78	Pass
7	0.078	1.291	6.0	0.081	1.936	4.16	Pass
8	0.004	0.359	1.1	0.006	0.538	1.03	Pass
9	0.131	N/A	N/A	0.103	N/A	N/A	N/A
10	0.003	0.287	0.9	0.004	0.430	0.82	Pass
11	0.031	0.556	5.5	0.036	0.834	4.26	Pass
12	0.002	0.239	0.9	0.003	0.359	0.96	Pass
13	0.045	0.359	12.6	0.050	0.538	9.30	Pass
14	0.003	N/A	N/A	0.004	N/A	N/A	N/A
15	0.036	N/A	N/A	0.040	N/A	N/A	N/A
16	0.003	N/A	N/A	0.004	N/A	N/A	N/A
17	0.037	N/A	N/A	0.043	N/A	N/A	N/A
18	0.003	N/A	N/A	0.004	N/A	N/A	N/A
19	0.037	N/A	N/A	0.042	N/A	N/A	N/A
20	0.003	N/A	N/A	0.003	N/A	N/A	N/A
21	0.035	N/A	N/A	0.041	N/A	N/A	N/A
22	0.002	N/A	N/A	0.003	N/A	N/A	N/A
23	0.035	N/A	N/A	0.039	N/A	N/A	N/A
24	0.004	N/A	N/A	0.005	N/A	N/A	N/A
25	0.037	N/A	N/A	0.041	N/A	N/A	N/A
26	0.004	N/A	N/A	0.010	N/A	N/A	N/A
27	0.038	N/A	N/A	0.041	N/A	N/A	N/A
28	0.003	N/A	N/A	0.004	N/A	N/A	N/A
29	0.039	N/A	N/A	0.043	N/A	N/A	N/A
30	0.003	N/A	N/A	0.005	N/A	N/A	N/A
31	0.042	N/A	N/A	0.045	N/A	N/A	N/A
32	0.004	N/A	N/A	0.006	N/A	N/A	N/A
33	0.037	N/A	N/A	0.039	N/A	N/A	N/A
34	0.004	N/A	N/A	0.005	N/A	N/A	N/A
35	0.040	N/A	N/A	0.042	N/A	N/A	N/A
36	0.003	N/A	N/A	0.005	N/A	N/A	N/A
37	0.036	N/A	N/A	0.038	N/A	N/A	N/A
38	0.004	N/A	N/A	0.006	N/A	N/A	N/A
39	0.028	N/A	N/A	0.029	N/A	N/A	N/A
40	0.008	N/A	N/A	0.012	N/A	N/A	N/A

Note: Measured reference fundamental current limits were applied for this test.




EUT: Uninterruptible power systems  
 Test category: Stage:2 1ph & B3ph(Rsce=33)  
 Test date: 2014-9-5  
 Test duration (min): 2.5  
 Comment: Line Mode  
 Customer: KSTAR

Tested by: KY  
 Test Margin: 100  
 Start time: 01:30:04 PM  
 End time: 01:32:56 PM  
 Data file name: WIN2106\_H-000010.cts\_data


Test Result: Pass Source qualification: Normal

Current & voltage waveforms



Harmonics and Class 2 limit line

European Limits



Test result: Pass Worst harmonic was #13 with 17.28 % of the limit.






H-5\_min\_phase : -16.1 Degree (Lagging)  
H-5\_max\_phase : -28.9 Degree (Lagging)  
H-5\_ave\_phase : 157.6 Degree (Leading)

H-5\_ave\_vector\_magnitude : 0.037 Amp  
H-5\_standard\_ave\_magnitude : 0.193 Amp  
H-5\_standard\_max\_magnitude : 0.196 Amp

## 7. VOLTAGE FLUCTUATION AND FLICKER MEASUREMENT

### 7.1. Block Diagram of Test Setup



(EUT: Uninterruptible power systems)

### 7.2. Measuring Standard

EN 61000-3-11: 2000

### 7.3. Operation Condition of EUT

Same as Section 4.4, except the test setup replaced as Section 7.1.

### 7.4. Measuring Results

**PASS.**


Please see the attached page.

### Flicker Test Summary (Phase A-Run time) per EN/IEC61000-3-11


EUT: UPS(YDC3320H) Tested by: YU  
 Test category: All parameters Test Margin: 100  
 Test date: 2014-1-14 Start time: PM 01:42:24 End time: PM 01:52:47  
 Test duration (min): 10 Data file name: WIN2106\_F-000011.cts\_data  
 Comment: FULL LOAD  
 Customer: KSTAR  
 Z-test Phase = (0.150 + j 0.150 Ohm) Neutral = (0.100 + j 0.100 Ohm)

Test Result: Pass  
 Status: Test Completed

#### Pst<sub>i</sub> and limit line



#### Plt and limit line



#### Parameter values recorded during the test:

Vrms at the end of test (Volt): 227.74

Time(mS) > dt:	0.0	Test limit (mS):	500.0	Pass
Highest dc (%):	1.65	Test limit (%):	3.30	Pass
Highest dmax (%):	1.39	Test limit (%):	4.00	Pass
Highest Pst (10 min. period):	0.246	Test limit:	1.000	Pass
Highest Plt (2 hr. period):	0.107	Test limit:	0.650	Pass

Calculated dmax(%): 1.854

Calculated dc(%): 2.203

Calculated Pst : 0.328

Calculated Pit : 0.143

The maximum permissible system impedance Zsys :

Z-phase A = 0.518 Ohm + j 0.324 Ohm                      (0.518 Ohm + 1030 H)

Z-neutral A = 0.345 Ohm + j 0.216 Ohm                    (0.345 Ohm + 687 H)


## Flicker Test Summary (Phase A-Run time) per EN/IEC61000-3-11

EUT: Uninterruptible power systems  
 Test category: All parameters  
 Test date: 2014-9-5  
 Test duration (min): 10  
 Comment: Lind Mode  
 Customer: KSTAR  
 Z-test Phase = (0.150 + j 0.150 Ohm) Neutral = (0.100 + j 0.100 Ohm)


Tested by: KY  
 Test Margin: 100  
 Start time: 01:42:24 PM  
 End time: 01:52:47 PM  
 Data file name: WIN2106\_F-000011.cts\_data

Test Result: Pass  
 Status: Test Completed

### Pst<sub>i</sub> and limit line



### Plt and limit line



### Parameter values recorded during the test:

Vrms at the end of test (Volt): 227.74

Time(mS) > dt:	0.0	Test limit (mS):	500.0	Pass
Highest dc (%):	1.65	Test limit (%):	3.30	Pass
Highest dmax (%):	1.39	Test limit (%):	4.00	Pass
Highest Pst (10 min. period):	0.246	Test limit:	1.000	Pass
Highest Plt (2 hr. period):	0.107	Test limit:	0.650	Pass

Calculated dmax(%): 1.854  
 Calculated dc(%): 2.203

Calculated Pst : 0.328  
Calculated Plt : 0.143

The maximum permissible system impedance Zsys :


Z-phase A = 0.518 Ohm + j 0.324 Ohm	(0.518 Ohm + 1030 H)
Z-neutral A = 0.345 Ohm + j 0.216 Ohm	(0.345 Ohm + 687 H)

## Flicker Test Summary (Phase B-Run time) per EN/IEC61000-3-11


EUT: Uninterruptible power systems		Tested by: KY
Test category: All parameters		Test Margin: 100
Test date: 2014-9-5	Start time: 01:42:24 PM	End time: 01:52:47 PM
Test duration (min): 10	Data file name: WIN2106_F-000011.cts_data	
Comment: Lind Mode		
Customer: KSTAR		
Z-test Phase = (0.150 + j 0.150 Ohm) Neutral = (0.100 + j 0.100 Ohm)		

Test Result: Pass  
Status: Test Completed

### Pst<sub>i</sub> and limit line



### Plt and limit line



### Parameter values recorded during the test:

Vrms at the end of test (Volt): 227.71

Time(mS) > dt:	0.0	Test limit (mS):	500.0	Pass
Highest dc (%):	0.74	Test limit (%):	3.30	Pass
Highest dmax (%):	-0.89	Test limit (%):	4.00	Pass
Highest Pst (10 min. period):	0.246	Test limit:	1.000	Pass
Highest Plt (2 hr. period):	0.107	Test limit:	0.650	Pass

Calculated dmax(%): -1.189  
Calculated dc(%): 0.986

Calculated Pst : 0.328  
Calculated Plt : 0.143

The maximum permissible system impedance Zsys :


Z-phase B = 1.277 Ohm + j 0.798 Ohm	(1.277 Ohm + 2540 H)
Z-neutral B = 0.851 Ohm + j 0.532 Ohm	(0.851 Ohm + 1694 H)

## Flicker Test Summary (Phase C-Run time) per EN/IEC61000-3-11


EUT: Uninterruptible power systems		Tested by: KY
Test category: All parameters		Test Margin: 100
Test date: 2014-9-5	Start time: 01:42:24 PM	End time: 01:52:47 PM
Test duration (min): 10	Data file name: WIN2106_F-000011.cts_data	
Comment: Lind Mode		
Customer: KSTAR		
Z-test Phase = (0.150 + j 0.150 Ohm) Neutral = (0.100 + j 0.100 Ohm)		

**Test Result: Pass**  
**Status: Test Completed**

### Pst<sub>i</sub> and limit line



### Plt and limit line



### Parameter values recorded during the test:

Vrms at the end of test (Volt): 227.70

Time(mS) > dt:	0.0	Test limit (mS):	500.0	Pass
Highest dc (%):	0.99	Test limit (%):	3.30	Pass
Highest dmax (%):	0.85	Test limit (%):	4.00	Pass
Highest Pst (10 min. period):	0.239	Test limit:	1.000	Pass
Highest Plt (2 hr. period):	0.105	Test limit:	0.650	Pass

Calculated dmax(%): 1.137  
 Calculated dc(%): 1.319  
 Calculated Pst : 0.319

Calculated Plt : 0.140

The maximum permissible system impedance Zsys :

Z-phase C = 1.329 Ohm + j 0.831 Ohm                    (1.329 Ohm + 2644 H)  
Z-neutral C = 0.886 Ohm + j 0.554 Ohm                (0.886 Ohm + 1763 H)

## 8. IMMUNITY PERFORMANCE CRITERIA DESCRIPTION

### Performance Level

The test results shall be classified in terms of the loss of function or degradation of performance of the equipment under test, relative to a performance level by its manufacturer or the requestor of the test, or the agreed between the manufacturer and the purchaser of the product.

Definition related to the performance level:

1. Based on the used product standard
2. Based on the declaration of the manufacturer, requestor or purchaser

#### Criterion A:

Definition: normal performance within limits specified by the manufacturer, requestor and purchaser.

The equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.

#### Criterion B:

Definition: temporary loss of function or degradation of performance which ceases after the disturbance ceases, and from which the equipment under test recovers its normal performance, without operator intervention.

After the test, the EUT shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed, after the application of the phenomena below a performance level specified by the manufacturer, when the EUT is used as intended. The performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is allowed. However, no change of operating state or stored data is allowed to persist after the test. If the minimum performance level (or the permissible performance loss) is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the EUT if used as intended.

#### Criterion C:

Definition: temporary loss of function or degradation of performance, the correction of which requires operator intervention.

Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions. Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.

## Criterion D

Definition: loss of function or degradation of performance, which is not recoverable, owing to damage to hardware or software, or loss of data.

## 9. ELECTROSTATIC DISCHARGE IMMUNITY TEST


### 9.1. Block Diagram of Test Setup

#### 9.1.1. Block diagram of connection between the EUT and simulators



(EUT: Uninterruptible power systems)

#### 9.1.2. Block diagram of ESD test setup



(EUT: Uninterruptible power systems)

### 9.2. Test Standard

IEC 61000-4-2:2008 (Air Discharge:  $\pm 8\text{kV}$ , Contact Discharge:  $\pm 4\text{kV}$ )

### 9.3. Severity Levels and Performance Criterion

#### 9.3.1. Severity level

Level	Test Voltage Contact Discharge (kV)	Test Voltage Air Discharge (kV)
1.	$\pm 2$	$\pm 2$
2.	$\pm 4$	$\pm 4$
3.	$\pm 6$	$\pm 8$
4.	$\pm 8$	$\pm 15$
X	Special	Special

## 2. GENERAL INFORMATION

### 2.1. Description of Device (EUT)

EUT	:	Uninterruptible power systems
Model Number	:	YDC3310S, YDC3310H, YDC3315S, YDC3315H, YDC3320S, YDC3320H, YDC3340H, YDC3330S, YDC3330H (Note: These models are identical in circuitry and electrical, mechanical and physical construction; the only differences are the power and model number. for trading purpose. We prepare YDC3320S/H, YDC3340H for test.)
Battery bank	:	YDC-BT battery bank series
Power supply	:	<p>MODEL: YDC3310S CAPACITY: 10kVA/9kW OUTPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 20A Max, 50/60Hz AC INPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 20A Max, 50/60Hz BATT INPUT: <math>\pm</math>120Vdc, 44A Icc: 6kA</p> <p>MODEL: YDC3310H CAPACITY: 10kVA/9kW OUTPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 20A Max, 50/60Hz AC INPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 20A Max, 50/60Hz BATT INPUT: <math>\pm</math>96/108/120Vdc, 55/49/44A Icc: 6kA</p> <p>MODEL: YDC3315S CAPACITY: 15kVA/13.5kW OUTPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 32A Max, 50/60Hz AC INPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 32A Max, 50/60Hz BATT INPUT: <math>\pm</math>120Vdc, 66A Icc: 6kA</p> <p>MODEL: YDC3315H CAPACITY: 15kVA/13.5kW OUTPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 32A Max, 50/60Hz AC INPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 32A Max, 50/60Hz BATT INPUT: <math>\pm</math>96/108/120Vdc, 83/74/66A Icc: 6kA</p> <p>MODEL: YDC3320S CAPACITY: 20kVA/18kW OUTPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 40A Max, 50/60Hz AC INPUT: 380/400/415Vac, 3<math>\Phi</math>+N+PE, 40A Max, 50/60Hz BATT INPUT: <math>\pm</math>120Vdc, 88A Icc: 6kA</p>

MODEL: YDC3320H  
CAPACITY: 20kVA/18kW  
OUTPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 40A Max, 50/60Hz  
AC INPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 40A Max, 50/60Hz  
BATT INPUT:  $\pm$ 96/108/120Vdc, 110/98/88A  
Icc: 6kA

MODEL: YDC3330S  
CAPACITY: 30kVA/27kW  
OUTPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 63A Max, 50/60Hz  
AC INPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 63A Max, 50/60Hz  
BATT INPUT:  $\pm$ 120Vdc, 143A  
Icc: 6kA

MODEL: YDC3330H  
CAPACITY: 30kVA/27kW  
OUTPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 63A Max, 50/60Hz  
AC INPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 63A Max, 50/60Hz  
BATT INPUT:  $\pm$ 96/108/120Vdc; 139/141/143A  
Icc: 6kA

MODEL: YDC3340H  
CAPACITY: 40kVA/36kW  
OUTPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 100A Max, 50/60Hz  
AC INPUT: 380/400/415Vac, 3 $\Phi$ +N+PE, 80A Max, 50/60Hz  
BATT INPUT:  $\pm$ 192/204/216/228/240Vdc, 119/112/106/100/95A  
Icc: 6kA

Test voltage : AC 380V/50Hz

Applicant : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.

Address : 4/F, No.1 Bldg, Software Park, Keji C. Rd. 2nd, Hi-Tech Industrial Zone, Shenzhen 518057, P.R.China

Manufacturer : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.

Address : 4/F, No.1 Bldg, Software Park, Keji C. Rd. 2nd, Hi-Tech Industrial Zone, Shenzhen 518057, P.R.China

Factory : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.  
GUANGMING BRANCH

Address : Kstar High Tech Park, Guangming High Technology Town, Gongming Street, Baoan District, Shenzhen City, Guangdong Province, P.R. China  
Shenzhen City, Guangdong Province, P.R. China

Date of receiver : January 09, 2014

Date of Test : January 09, 2014 to January 21, 2014

## 2.2. Description of Support Device

N/A

### 2.3. Description of Test Facility

Site Description

EMC Lab. : Accredited by CNAS, 2013.10.29  
The certificate is valid until 2016.10.28  
The Laboratory has been assessed and proved to be in compliance with CNAS-CL01: 2006 (identical to ISO/IEC17025: 2005)  
The Certificate Registration Number is L2291.

Accredited by TUV Rheinland Guangzhou 2010.5.25  
The Laboratory has been assessed according to the requirements ISO/IEC 17025

Accredited by FCC, April 17, 2013  
The Certificate Registration Number. is 709623.

Accredited by Industry Canada, November 15, 2010  
The Certificate Registration Number. is 46405-4480

Name of Firm : SHENZHEN EMTEK CO., LTD  
Site Location : Bldg 69, Majialong Industry Zone,  
Nanshan District, Shenzhen, Guangdong, China

### 2.4. Measurement Uncertainty

Test Item	Uncertainty
Conducted Emission Uncertainty	: 3.16dB(9k~150kHz Conduction 2#) 2.90dB(150k-30MHz Conduction 2#)
Radiated Emission Uncertainty (10m Chamber)	: 3.96dB (30M~1GHz Polarize: H) 4.04dB (30M~1GHz Polarize: V)
Uncertainty for Flicker test	: 0.07%
Uncertainty for Harmonic test	: 1.8%
Uncertainty for C/S Test	: 1.45(Using CDN Test)
Uncertainty for R/S Test	: 2.10dB(80MHz-200MHz) 1.76dB(200MHz-1000MHz)
Uncertainty for test site temperature and humidity	: 0.6°C 4%

### 3. MEASURING DEVICE AND TEST EQUIPMENT

#### 3.1. For Conducted Emission Measurement

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Test Receiver	Rohde & Schwarz	ESCS30	828985/018	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	L.I.S.N.	Schwarzbeck	NNLK8129	8129-203	May 29, 2013	1 Year
<input type="checkbox"/>	L.I.S.N.	ROHDE & SCHWARZ	ESH3-Z6	100011	May 29, 2013	1 Year
<input type="checkbox"/>	L.I.S.N.	ROHDE & SCHWARZ	ESH3-Z6	100253	May 29, 2013	1 Year
<input type="checkbox"/>	L.I.S.N.	ROHDE & SCHWARZ	ESH3-Z5	100191	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	50Ω Coaxial Switch	Anritsu	MP59B	M20531	N/A	N/A
<input checked="" type="checkbox"/>	Pulse Limiter	Rohde & Schwarz	ESH3-Z2	100006	May 29, 2013	1 Year
<input type="checkbox"/>	Current probe	Rohde & Schwarz	EZ-17	0816.2063.02	May 29, 2013	1 Year

#### 3.2. For Radiated Emission Measurement

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	EMI TEST RECEIVER	R&S/DE	ESR3	1316.300K03-101707-Z 1	Dec.14, 2013	1Year
<input checked="" type="checkbox"/>	EMI TEST RECEIVER	R&S/DE	ESCI3	1166.5950K03-101384- Bw	Dec.14, 2013	1Year
<input checked="" type="checkbox"/>	Frequency Analyser	R&S/DE	FSV40	132.1.3008K39-100967- AP	Dec.14, 2013	1Year
<input checked="" type="checkbox"/>	Broadband Antenna (30M-3GHz)	Schwarzbeck/D E	VULP916 3	659/660/661	Dec.14, 2013	1Year
<input type="checkbox"/>	Horn Antenna (1G-18GHz)	Schwarzbeck/D E	BBHA912 0D	1177/1178	Dec.14, 2013	1Year
<input type="checkbox"/>	Horn Antenna (15G-26.5GHz)	Schwarzbeck/D E	BBHA917 0	547	Dec.14, 2013	1Year
<input type="checkbox"/>	Horn Antenna (26.5G-40GHz)	AHS/USA	SAS-573	184/185	Dec.14, 2013	1Year
<input checked="" type="checkbox"/>	Pre-Amplifier (10M-1GHz 40dB)	Lunar EM	PM01-1-4 0	N/A	Dec.14, 2013	1Year
<input type="checkbox"/>	Pre-Amplifier (1G-18GHz 40dB)	Lunar EM	PM1-18-4 0	J101121229001	Dec.14, 2013	1Year
<input type="checkbox"/>	Pre-Amplifier (1G-18GHz 48dB)	Lunar EM	PM1-18-4 8	DS131115120D1177	Dec.14, 2013	1Year
<input type="checkbox"/>	Pre-Amplifier(18G-26.5GHz 40dB)	Lunar EM	PM18-26- 40	J1012131010001	Dec.14, 2013	1Year
<input type="checkbox"/>	Pre-Amplifier (18G-26.5GHz 48dB)	Lunar EM	PM18-26- 48	J1013131010001	Dec.14, 2013	1Year
<input type="checkbox"/>	Pre-Amplifier(26.5 G-40GHz 40dB)	Lunar EM	PM26-40- 40	J1013131028001	Dec.14, 2013	1Year

### 3.3. For Harmonic Current / Flicker Measurement

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	45KVA AC Power source	Teseq/Germany	NSG 1007-45/45KVA	1305A02873	April 25, 2013	1 Year
<input checked="" type="checkbox"/>	Signal conditioning Unit	Teseq/Germany	CCN 1000-3	1305A02873	April 25, 2013	1 Year
<input checked="" type="checkbox"/>	Three phase impedance network	Teseq/Germany	INA2197/37A	1305A02873	April 25, 2013	1 Year
<input checked="" type="checkbox"/>	Three phase impedance network	Teseq/Germany	INA 2196/75A	1305A02874	April 25, 2013	1 Year
<input type="checkbox"/>	Proflin 2100 AC Switching Unit	Teseq/Germany	NSG2200-3	A22714	April 25, 2013	1 Year

### 3.4. For Electrostatic Discharge Immunity Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	ESD Tester	TESEQ AG	NSG 438A	130	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	Impulse Module	TESEQ AG	INA 4380-150pF/330Ohm	403-550/1712	May 29, 2013	1 Year

### 3.5. For RF Strength Susceptibility Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Signal Generator	Agilent	N5181A	MY50145187	Nov 04, 2013	1 Year
<input checked="" type="checkbox"/>	RF Power Meter. Dual Channel	BOONTON	4232A	10539	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	50ohm Diode Power Sensor	BOONTON	51011EMC	34236/34238	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	Field Strength Meter	DARE	RSS1006A	10I00037SO2 2	Nov 04, 2013	1 Year
<input checked="" type="checkbox"/>	50ohm Diode Power Sensor	BOONTON	51011EMC	36164	Nov 04, 2013	1 Year
<input checked="" type="checkbox"/>	Power Amplifier	MILMEGA	80RF1000-175	1059345	May 29, 2013	1 Year
<input type="checkbox"/>	Power Amplifier	MILMEGA	AS0102-55	1018770	May 29, 2013	1 Year
<input type="checkbox"/>	Power Amplifier	MILMEGA	AS1860-50	1059346	Nov 04, 2013	1 Year
<input checked="" type="checkbox"/>	Log.-Per. Antenna	SCHWARZBECK	VULP 9118E	N/A	May 11, 2013	1 Year
<input type="checkbox"/>	Broad-Band Horn Antenna	SCHWARZBECK	STLP 9149	9149-227	Nov 04, 2013	1 Year
<input checked="" type="checkbox"/>	Multi-function interface system	DARE	CTR1009B	12I00250SNO 72	N/A	N/A
<input checked="" type="checkbox"/>	Automatic switch group	DARE	RSW1004A	N/A	N/A	N/A

### 3.6. For Electrical Fast Transient/Burst Immunity Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Burst Tester	HAEFELY	PEFT4010	080981-16	May 29, 2013	1Year
<input type="checkbox"/>	Coupling Clamp	HAEFELY	IP-4A	147147	May 29, 2013	1Year
<input checked="" type="checkbox"/>	Three phase CDN	Teseq	CDN 163	202	May 29, 2013	1 Year

### 3.7. For Surge Immunity Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Surge Controller	HAEFELY	Psurge 8000	174031	May 29, 2013	1Year
<input checked="" type="checkbox"/>	Impulse Module	HAEFELY	PIM 100	174124	May 29, 2013	1Year
<input checked="" type="checkbox"/>	Coupling Decoupling Filter	HAEFELY	PCD 130	172181	May 29, 2013	1Year

### 3.8. For Injected Current Susceptibility Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Simulator	EMTEST	CWS500C	0900-12	May 29, 2013	1Year
<input type="checkbox"/>	CDN	EMTEST	CDN-M2	5100100100	May 29, 2013	1Year
<input checked="" type="checkbox"/>	CDN	EMTEST	CDN-M3	0900-11	May 29, 2013	1Year
<input type="checkbox"/>	Injection Clamp	EMTEST	F-2031-23MM	368	May 29, 2013	1Year
<input checked="" type="checkbox"/>	Attenuator	EMTEST	ATT6	0010222A	May 29, 2013	1Year
<input checked="" type="checkbox"/>	Three phase CDN	Teseq	CDN M332S	32655	May 29, 2013	1 Year
<input type="checkbox"/>	Three phase CDN	Teseq	CDN M432S	33670	May 29, 2013	1 Year
<input checked="" type="checkbox"/>	Three phase CDN	Teseq	CDN M432-3LNS	34048	May 29, 2013	1 Year
<input type="checkbox"/>	Three phase CDN	Teseq	CDN M532S	33799	May 29, 2013	1 Year

### 3.9. For Magnetic Field Immunity Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Magnetic Field Tester	HAEFELY	MAG100	250040.1	May 29, 2013	1Year

### 3.10. For Voltage Dips and Interruptions Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	45KVA AC Power source	Teseq/Germany	NSG 1007-45/45KVA	1305A02873	April 25, 2013	1 Year
<input type="checkbox"/>	Signal conditioning Unit	Teseq/Germany	CCN 1000-3	1305A02873	April 25, 2013	1 Year
<input type="checkbox"/>	Three phase impedance network	Teseq/Germany	INA2197/37A	1305A02873	April 25, 2013	1 Year
<input type="checkbox"/>	Three phase impedance network	Teseq/Germany	INA 2196/75A	1305A02874	April 25, 2013	1 Year
<input checked="" type="checkbox"/>	Proflin 2100 AC Switching Unit	Teseq/Germany	NSG2200-3	A22714	April 25, 2013	1 Year


### 3.11. Low Frequency Signals Test

Used	Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal. Interval
<input checked="" type="checkbox"/>	Programmable AC Source	CHROMA	6530	/	May 29, 2013	1Year

## 4. CONDUCTED EMISSION MEASUREMENT

### 4.1. Block Diagram of Test Setup

For AC Mains:



(EUT: Uninterruptible power systems)

### 4.2. Measuring Standard

EN62040-2: 2006, IEC 62040-2:2005 Category C2  
Power Line Conducted Emission Limits

Frequency (MHz)	Limit (dB $\mu$ V)	
	Quasi-peak Level	Average Level
0.15 ~ 0.50	79	66
0.50 ~ 30.00	73	60

NOTE1- The lower limit shall apply at the transition frequencies.

### 4.3. EUT Configuration on Measurement

The following equipments are installed on Conducted Emission Measurement to meet EN 62040-2 requirements and operating in a manner which tends to maximize its emission characteristics in a normal application.

Uninterruptible power systems (EUT)  
 Model Number : YDC3320S/H  
 Serial Number : N/A

### 4.4. Operating Condition of EUT

- 4.4.1. Setup the EUT as shown on Section 4.1.
- 4.4.2. Turn on the power of all equipments.
- 4.4.3. Let the EUT work in measuring mode (Line mode/ Battery mode) and measure it.

#### 4.5. Test Procedure

The EUT is put on the plane 0.1m high above the ground by insulating support and connected to the AC mains through Line Impedance Stability Network (L.I.S.N) or connected to the telecommunication port through an impedance stabilization network (ISN). L.I.S.N provided a 50ohm coupling impedance for the tested equipments AC mains port, I.S.N provided a common mode (asymmetric mode) impedance of 150  $\Omega$  to the telecommunication port under test. Both sides of AC line and telecommunication line are investigated to find out the maximum conducted emission according to the EN 62040-2 regulations during conducted emission measurement.


The bandwidth of the field strength meter (R&S Test Receiver ESCS30) is set at 9KHz in 150KHz~30MHz and 200Hz in 9KHz~150KHz.

The frequency range from 150kHz to 30MHz is investigated.

#### 4.6. Measuring Results

**PASS.**

Please refer to the following pages.



Site: Conduction #2

Phase: **Lf**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53%

Mode: FULL LOAD

Note: LINE MODE

No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1		0.1500	71.08	0.00	71.08	79.00	-7.92	QP	
2		0.1500	60.73	0.00	60.73	66.00	-5.27	AVG	
3		0.6150	58.60	0.00	58.60	73.00	-14.40	QP	
4		0.6150	48.47	0.00	48.47	60.00	-11.53	AVG	
5		4.0700	61.94	0.00	61.94	73.00	-11.06	QP	
6		4.0700	50.58	0.00	50.58	60.00	-9.42	AVG	
7		5.0200	61.26	0.00	61.26	73.00	-11.74	QP	
8		5.0200	52.48	0.00	52.48	60.00	-7.52	AVG	
9		9.7300	63.00	0.00	63.00	73.00	-10.00	QP	
10	*	9.7300	55.60	0.00	55.60	60.00	-4.40	AVG	
11		29.8750	58.48	0.00	58.48	73.00	-14.52	QP	
12		29.8750	48.70	0.00	48.70	60.00	-11.30	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **L2**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53 %

Mode: FULL LOAD

Note: LINE MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.1750	64.83	0.00	64.83	79.00	-14.17	QP	
2	0.1750	57.18	0.00	57.18	66.00	-8.82	AVG	
3	0.5950	62.42	0.00	62.42	73.00	-10.58	QP	
4	0.5950	49.43	0.00	49.43	60.00	-10.57	AVG	
5	1.2500	50.95	0.00	50.95	73.00	-22.05	QP	
6	1.2500	36.33	0.00	36.33	60.00	-23.67	AVG	
7	4.1700	64.82	0.00	64.82	73.00	-8.18	QP	
8	4.1700	52.83	0.00	52.83	60.00	-7.17	AVG	
9	9.3700	63.68	0.00	63.68	73.00	-9.32	QP	
10 *	9.3700	53.50	0.00	53.50	60.00	-6.50	AVG	
11	17.5500	52.01	0.00	52.01	73.00	-20.99	QP	
12	17.5500	40.94	0.00	40.94	60.00	-19.06	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE




Site Conduction #2  
 Limit: (CE)EN62040-2 C2\_QP  
 Mode: FULL LOAD  
 Note: LINE MODE

Phase: **L3**  
 Power: AC 380V/50Hz

Temperature: 22  
 Humidity: 53 %

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.1550	66.23	0.00	66.23	79.00	-12.77	QP	
2	0.1550	60.75	0.00	60.75	66.00	-5.25	AVG	
3	0.5950	63.60	0.00	63.60	73.00	-9.40	QP	
4	0.5950	54.09	0.00	54.09	60.00	-5.91	AVG	
5	1.1400	55.76	0.00	55.76	73.00	-17.24	QP	
6	1.1400	42.01	0.00	42.01	60.00	-17.99	AVG	
7	4.1800	65.60	0.00	65.60	73.00	-7.40	QP	
8 *	4.1800	55.91	0.00	55.91	60.00	-4.09	AVG	
9	9.9700	59.91	0.00	59.91	73.00	-13.09	QP	
10	9.9700	51.57	0.00	51.57	60.00	-8.43	AVG	
11	16.0000	53.40	0.00	53.40	73.00	-19.60	QP	
12	16.0000	43.65	0.00	43.65	60.00	-16.35	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **N**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53 %

Mode: FULL LOAD

Note: LINE MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.1750	70.87	0.00	70.87	79.00	-8.13	QP	
2 *	0.1750	62.33	0.00	62.33	66.00	-3.67	AVG	
3	0.3450	59.14	0.00	59.14	79.00	-19.86	QP	
4	0.3450	50.87	0.00	50.87	66.00	-15.13	AVG	
5	3.9600	61.81	0.00	61.81	73.00	-11.19	QP	
6	3.9600	55.89	0.00	55.89	60.00	-4.11	AVG	
7	5.0000	64.17	0.00	64.17	73.00	-8.83	QP	
8	5.0000	53.83	0.00	53.83	60.00	-6.17	AVG	
9	8.5700	66.57	0.00	66.57	73.00	-6.43	QP	
10	8.5700	55.33	0.00	55.33	60.00	-4.67	AVG	
11	16.1750	56.30	0.00	56.30	73.00	-16.70	QP	
12	16.1750	49.10	0.00	49.10	60.00	-10.90	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **L1**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53%

Mode: FULL LOAD

Note: BAT MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.2300	71.16	0.00	71.16	79.00	-7.84	QP	
2	0.2300	58.81	0.00	58.81	66.00	-7.19	AVG	
3	0.4600	54.41	0.00	54.41	79.00	-24.59	QP	
4	0.4600	45.83	0.00	45.83	66.00	-20.17	AVG	
5	3.5900	64.14	0.00	64.14	73.00	-8.86	QP	
6	3.5900	52.80	0.00	52.80	60.00	-7.20	AVG	
7	5.0600	64.63	0.00	64.63	73.00	-8.37	QP	
8	5.0600	52.80	0.00	52.80	60.00	-7.20	AVG	
9	9.7900	65.95	0.00	65.95	73.00	-7.05	QP	
10 *	9.7900	54.61	0.00	54.61	60.00	-5.39	AVG	
11	29.7000	55.56	0.00	55.56	73.00	-17.44	QP	
12	29.7000	49.54	0.00	49.54	60.00	-10.46	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **L2**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53 %

Mode: FULL LOAD

Note: BAT MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.2100	71.98	0.00	71.98	79.00	-7.02	QP	
2	0.2100	59.22	0.00	59.22	66.00	-6.78	AVG	
3	0.3450	60.92	0.00	60.92	79.00	-18.08	QP	
4	0.3450	53.08	0.00	53.08	66.00	-12.92	AVG	
5	3.8800	65.06	0.00	65.06	73.00	-7.94	QP	
6	3.8800	54.47	0.00	54.47	60.00	-5.53	AVG	
7	5.0400	62.65	0.00	62.65	73.00	-10.35	QP	
8	5.0400	51.27	0.00	51.27	60.00	-8.73	AVG	
9	9.4300	66.76	0.00	66.76	73.00	-6.24	QP	
10 *	9.4300	55.31	0.00	55.31	60.00	-4.69	AVG	
11	29.5000	53.47	0.00	53.47	73.00	-19.53	QP	
12	29.5000	47.26	0.00	47.26	60.00	-12.74	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **L3**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz


Humidity: 53 %

Mode: FULL LOAD

Note: BAT MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.2100	70.48	0.00	70.48	79.00	-8.52	QP	
2	0.2100	58.52	0.00	58.52	66.00	-7.48	AVG	
3	0.4050	58.32	0.00	58.32	79.00	-20.68	QP	
4	0.4050	47.72	0.00	47.72	66.00	-18.28	AVG	
5	3.9100	66.08	0.00	66.08	73.00	-6.92	QP	
6	3.9100	54.33	0.00	54.33	60.00	-5.67	AVG	
7	5.0300	64.10	0.00	64.10	73.00	-8.90	QP	
8 *	5.0300	55.10	0.00	55.10	60.00	-4.90	AVG	
9	9.0900	61.51	0.00	61.51	73.00	-11.49	QP	
10	9.0900	52.52	0.00	52.52	60.00	-7.48	AVG	
11	17.6000	59.93	0.00	59.93	73.00	-13.07	QP	
12	17.6000	54.04	0.00	54.04	60.00	-5.96	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE



Site Conduction #2

Phase: **N**

Temperature: 22

Limit: (CE)EN62040-2 C2\_QP

Power: AC 380V/50Hz

Humidity: 53 %

Mode: FULL LOAD

Note: BAT MODE

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.2100	59.69	0.00	59.69	79.00	-19.31	QP	
2	0.2100	49.39	0.00	49.39	66.00	-16.61	AVG	
3	0.3650	54.65	0.00	54.65	79.00	-24.35	QP	
4	0.3650	42.51	0.00	42.51	66.00	-23.49	AVG	
5	4.0900	63.65	0.00	63.65	73.00	-9.35	QP	
6	4.0900	51.07	0.00	51.07	60.00	-8.93	AVG	
7	5.1500	64.79	0.00	64.79	73.00	-8.21	QP	
8	5.1500	55.42	0.00	55.42	60.00	-4.58	AVG	
9	9.0000	64.84	0.00	64.84	73.00	-8.16	QP	
10 *	9.0000	55.95	0.00	55.95	60.00	-4.05	AVG	
11	17.5000	53.28	0.00	53.28	73.00	-19.72	QP	
12	17.5000	47.68	0.00	47.68	60.00	-12.32	AVG	


\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HE

File :KSTAR  
100.0 dBuV

Data :#1243

Date: 2014/08/21

Time: 10:08:22



Site Conduction #2

Phase: **L1**

Temperature: 26

Limit: (CE)EN62040-2 C2\_QP

Power: AC380/50Hz

Humidity: 55 %

EUT: UPS

MN: YDC3340H


Mode: LINE MODE

Note:

No.	Mk.	Freq.	Reading Level	Correct Factor	Measurement	Limit	Over	Detector	Comment
		MHz	dBuV	dB	dBuV	dBuV	dB		
1		0.1600	70.83	0.00	70.83	79.00	-8.17	QP	
2	*	0.1600	61.86	0.00	61.86	66.00	-4.14	AVG	
3		0.1800	67.97	0.00	67.97	79.00	-11.03	QP	
4		0.1800	61.18	0.00	61.18	66.00	-4.82	AVG	
5		2.8800	64.22	0.00	64.22	73.00	-8.78	QP	
6		2.8800	50.75	0.00	50.75	60.00	-9.25	AVG	
7		3.1731	63.59	0.00	63.59	73.00	-9.41	QP	
8		3.1731	53.21	0.00	53.21	60.00	-6.79	AVG	
9		7.0997	64.53	0.00	64.53	73.00	-8.47	QP	
10		7.0997	53.38	0.00	53.38	60.00	-6.62	AVG	
11		8.2400	66.90	0.00	66.90	73.00	-6.10	QP	
12		8.2400	53.62	0.00	53.62	60.00	-6.38	AVG	

\*:Maximum data    x:Over limit    | :over margin    Comment: Factor build in receiver.    Operator: HJ

File:KSTAR      Data #1244      Date: 2014/08/21      Time: 10:11:05  
 100.0 dBuV



Site: Conduction #2      Phase: **L2**      Temperature: 26  
 Limit: (CE)EN62040-2 C2\_QP      Power: AC380/50Hz      Humidity: 55 %  
 EUT: UPS  
 M/N: YDC3340H  
 Mode: LINE MODE  
 Note:

No. Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measurement dBuV	Limit dBuV	Over dB	Detector	Comment
1	0.1600	72.08	0.00	72.08	79.00	-6.92	QP	
2	0.1600	61.84	0.00	61.84	66.00	-4.16	AVG	
3	0.1800	69.39	0.00	69.39	79.00	-9.61	QP	
4	0.1800	60.51	0.00	60.51	66.00	-5.49	AVG	
5	3.4600	66.48	0.00	66.48	73.00	-6.52	QP	
6	3.4600	55.71	0.00	55.71	60.00	-4.29	AVG	
7	7.7800	66.62	0.00	66.62	73.00	-6.38	QP	
8 *	7.7800	55.91	0.00	55.91	60.00	-4.09	AVG	
9	8.9300	66.22	0.00	66.22	73.00	-6.78	QP	
10	8.9300	55.90	0.00	55.90	60.00	-4.10	AVG	
11	17.7250	57.53	0.00	57.53	73.00	-15.47	QP	
12	17.7250	45.85	0.00	45.85	60.00	-14.15	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver,    Operator: HJ

File: KSTAR      Data: #1245      Date: 2014/08/21      Time: 10:13:51  
 100.0 dBuV



Site: Conduction #2

Phase: **L3**

Temperature: 26

Limit: (CE)EN62040-2 C2\_QP

Power: AC380/50Hz

Humidity: 66 %

EUT: UPS

M/N: YDC3340H


Mode: LINE MODE

Note:

No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1		0.1600	73.44	0.00	73.44	79.00	-5.56	QP	
2	*	0.1600	62.54	0.00	62.54	66.00	-3.46	AVG	
3		0.1800	70.16	0.00	70.16	79.00	-8.84	QP	
4		0.1800	61.87	0.00	61.87	66.00	-4.13	AVG	
5		0.2000	67.44	0.00	67.44	79.00	-11.56	QP	
6		0.2000	58.57	0.00	58.57	66.00	-7.43	AVG	
7		3.3500	54.07	0.00	54.07	73.00	-18.93	QP	
8		3.3500	45.39	0.00	45.39	60.00	-14.61	AVG	
9		7.0900	64.54	0.00	64.54	73.00	-8.46	QP	
10		7.0900	54.54	0.00	54.54	60.00	-5.46	AVG	
11		8.1400	65.96	0.00	65.96	73.00	-7.04	QP	
12		8.1400	55.23	0.00	55.23	60.00	-4.77	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HJ

File :KSTAR                      Data #1242                      Date: 2014/08/21                      Time: 10:04:08




Site Conduction #2                      Phase: **N**                      Temperature: 26  
 Limit: (CE)EN62040-2 C2\_QP                      Power: AC380/50Hz                      Humidity: 55 %  
 EUT: UPS  
 M/N: YDC3340H  
 Mode: LINE MODE  
 Note:

No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Over		
		MHz	Level	Factor	ment			Detector	Comment
			dBuV	dB	dBuV	dBuV	dB		
1		0.1800	68.44	0.00	68.44	79.00	-10.56	QP	
2		0.1800	58.83	0.00	58.83	66.00	-7.17	AVG	
3		0.2150	67.92	0.00	67.92	79.00	-11.08	QP	
4		0.2150	57.97	0.00	57.97	66.00	-8.03	AVG	
5		2.7700	64.05	0.00	64.05	73.00	-8.95	QP	
6		2.7700	54.23	0.00	54.23	60.00	-5.77	AVG	
7		5.3300	64.00	0.00	64.00	73.00	-9.00	QP	
8	*	5.3300	55.68	0.00	55.68	60.00	-4.32	AVG	
9		7.4600	66.08	0.00	66.08	73.00	-6.92	QP	
10		7.4600	52.38	0.00	52.38	60.00	-7.62	AVG	
11		12.8250	61.75	0.00	61.75	73.00	-11.25	QP	
12		12.8250	51.45	0.00	51.45	60.00	-8.55	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver.    Operator: HJ



File :KSTAR Data #1247 Date: 2014/08/21 Time: 10:19:52  
 100.0 dBuV



Site Conduction #2 Phase: **L2** Temperature: 25  
 Limit: (CE)EN62040-2 C2\_QP Power: AC380/50Hz Humidity: 55 %  
 EUT: UPS  
 M/N: YDC3340H  
 Mode: BAT MODE  
 Note:

No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Over		
		MHz	Level	Factor	ment			Detector	Comment
			dBuV	dB	dBuV	dBuV	dB		
1		0.1500	64.21	0.00	64.21	79.00	-14.79	QP	
2	*	0.1500	57.44	0.00	57.44	66.00	-8.56	AVG	
3		0.2150	58.98	0.00	58.98	79.00	-20.02	QP	
4		0.2150	49.99	0.00	49.99	66.00	-16.01	AVG	
5		2.4700	61.01	0.00	61.01	73.00	-11.99	QP	
6		2.4700	49.01	0.00	49.01	60.00	-10.99	AVG	
7		3.5500	61.48	0.00	61.48	73.00	-11.52	QP	
8		3.5500	49.77	0.00	49.77	60.00	-10.23	AVG	
9		5.9100	58.80	0.00	58.80	73.00	-14.20	QP	
10		5.9100	48.98	0.00	48.98	60.00	-11.02	AVG	
11		7.6900	59.87	0.00	59.87	73.00	-13.13	QP	
12		7.6900	49.66	0.00	49.66	60.00	-10.34	AVG	


\*:Maximum data x:Over limit l:over margin Comment: Factor build in receiver. Operator: HJ

File :KSTAR  
100.0 dBuV

Data :#1246

Date: 2014/08/21

Time: 10:17:11



Site: Conduction #2

Phase: **L3**

Temperature: 26

Limit: (CE)EN62040-2 C2\_QP

Power: AC380/50Hz

Humidity: 55 %

EUT: UPS

MN: YDC3340H

Mode: BAT MODE

Note:

No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Over dB	Detector	Comment
1	*	0.7050	53.63	0.00	53.63	60.00	-6.37	AVG	
2		0.7350	59.91	0.00	59.91	73.00	-13.09	QP	
3		2.5000	59.10	0.00	59.10	73.00	-13.90	QP	
4		2.5000	46.50	0.00	46.50	60.00	-13.50	AVG	
5		3.3700	50.67	0.00	50.67	60.00	-9.33	AVG	
6		3.7300	59.19	0.00	59.19	73.00	-13.81	QP	
7		7.6463	55.16	0.00	55.16	73.00	-17.84	QP	
8		8.9163	45.07	0.00	45.07	60.00	-14.93	AVG	
9		14.8250	48.78	0.00	48.78	60.00	-11.22	AVG	
10		18.3000	56.05	0.00	56.05	73.00	-16.95	QP	
11		20.7037	56.58	0.00	56.58	73.00	-16.42	QP	
12		21.1250	47.81	0.00	47.81	60.00	-12.19	AVG	

\*:Maximum data    x:Over limit    !:over margin    Comment: Factor build in receiver,    Operator: HJ

File :KSTAR  
100.0 dBuV

Data #1249

Date: 2014/08/21

Time: 10:26:24



Site Conduction #2

Phase: **N**

Temperature: 26

Limit: (CE)EN62040-2 C2\_QP

Power: AC380/50Hz

Humidity: 55 %

EUT: UPS

M/N: YDC3340H

Mode: BAT MODE

Note:

No.	Mk.	Freq.	Reading Level	Correct Factor	Measurement	Limit	Over	Detector	Comment
		MHz	dBuV	dB	dBuV	dBuV	dB		
1		0.1500	56.18	0.00	56.18	79.00	-22.82	QP	
2		0.1500	50.05	0.00	50.05	66.00	-15.95	AVG	
3		0.5050	52.91	0.00	52.91	73.00	-20.09	QP	
4		0.5050	42.36	0.00	42.36	60.00	-17.64	AVG	
5		2.2700	59.28	0.00	59.28	73.00	-13.72	QP	
6		2.2700	49.31	0.00	49.31	60.00	-10.69	AVG	
7	*	5.6233	65.75	0.00	65.75	73.00	-7.25	QP	
8		5.6233	49.21	0.00	49.21	60.00	-10.79	AVG	
9		7.1700	65.19	0.00	65.19	73.00	-7.81	QP	
10		7.1700	51.70	0.00	51.70	60.00	-8.30	AVG	
11		14.5000	47.01	0.00	47.01	73.00	-25.99	QP	
12		14.5000	37.63	0.00	37.63	60.00	-22.37	AVG	

\*:Maximum data    x:Over limit    l:over margin    Comment: Factor build in receiver.    Operator: HJ

## 5. RADIATED EMISSION MEASUREMENT


### 5.1. Block Diagram of Test

#### 5.1.1. Block diagram of connection between the EUT and simulators



(EUT: Uninterruptible power systems)

#### 5.1.2. Block diagram of test setup (In chamber)



(EUT: Uninterruptible power systems)

### 5.2. Measuring Standard

EN62040-2: 2006 Category C2

### 5.3. Radiated Emission Limits

All emanations from device or system, including any network of conductors and apparatus connected thereto, shall not exceed the level of field strengths specified below:

FREQUENCY (MHz)	DISTANCE (Meters)	FIELD STRENGTHS LIMIT (dB $\mu$ V/m)
30 ~ 230	10	40
230 ~ 1000	10	47

Note: (1) The smaller limit shall apply at the combination point between two frequency bands.  
(2) Distance refers to the distance in meters between the measuring instrument antenna and the closed point of any part of the EUT.

### 5.4. EUT Configuration on Test

The EN 62040-2 regulations test method must be used to find the maximum emission during radiated emission measurement.

### 5.5. Operating Condition of EUT

5.5.1. Turn on the power.

5.5.2. After that, let the EUT work in test mode (Line mode/Battery mode) and measure it.

### 5.6. Test Procedure

The EUT is placed on a turn table which is 0.1m high above the ground. The turn table can rotate 360 degrees to determine the position of the maximum emission level. The EUT is set 10 meters away from the receiving antenna which is mounted on a antenna tower. The antenna can be moved up and down from 1 to 4 meters to find out the maximum emission level. Bilog antenna (calibrated by Dipole Antenna) is used as a receiving antenna. Both horizontal and vertical polarization of the antenna are set on test.

The bandwidth of the Receiver is set at 120kHz.

### 5.7. Measuring Results

**PASS.**

The frequency range from 30MHz to 1000MHz is investigated.

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Horizontal
Tester: CSL	Model: YDC3320H	Mode: FULL LOAD
Test Time: 2014/1/17 10:10	Temperature: 20	Humidity: 53
Power: AC 380V/50Hz	Test Distance: 10M	EUT: Uninterruptible Power supply
Note: LINE MOAE		

## 2. Chart




## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Limit1	Margin Peak	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB(uV/m)	dB(uV/m)	dB	dB(uV)	dB(uV/m)	dB	dB	Degree	cm	
1	30.97	41.19	36.1	-32.91	74.1	40	1.19	-3.9			Pass
2	63.88	35.75	31.7	-31.18	66.93	40	-4.25	-8.3			Pass
3	108.41	40.73	36.4	-30.44	71.17	40	0.73	-3.6			Pass
4	174.24	35.41	32.8	-32.55	67.96	40	-4.59	-7.2			Pass
5	218.77	30.1	26.9	-30.43	60.53	40	-9.9	-13.1			Pass
6	253.62	27.03	24.3	-28.68	55.71	47	-19.97	-22.7			Pass

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Vertical
Tester: CSL	Model: YDC3320H	Mode: FULL LOAD
Test Time: 2014/1/17 10:10	Temperature: 20	Humidity: 53
Power: AC 380V/50Hz	Test Distance: 10M	EUT: Uninterruptible Power supply
Note: LINE MODE		

## 2. Chart



## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Limit1	Margin Peak	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB(uV/m)	dB(uV/m)	dB	dB(uV)	dB(uV/m)	dB	dB	Degree	cm	
1	30.97	42.4	38.6	-32.85	75.25	40	2.4	-1.4			Pass
2	112.29	40.19	36.1	-31.73	71.92	40	0.19	-3.9			Pass
3	131.65	38.57	34.7	-35.02	73.59	40	-1.43	-5.3			Pass
4	147.14	36.19	33.2	-35.34	71.53	40	-3.81	-6.8			Pass
5	180.05	35.5	32.9	-33.2	68.7	40	-4.5	-7.1			Pass
6	197.48	39.84	35.4	-31.54	71.38	40	-0.16	-4.6			Pass

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Horizontal
Tester: CSL	Model: YDC3320H	Mode: FULL LOAD
Test Time: 2014/1/17 10:17	Temperature: 20	Humidity: 53
Power: AC 380V/50Hz	Test Distance: 10M	EUT: Uninterruptible Power supply
Note: BAT MOAE		

## 2. Chart




## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Limit1	Margin Peak	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB (uV/m)	dB (uV/m)	dB	dB (uV)	dB (uV/m)	dB	dB	Degree	cm	
1	30.97	38.61	34.2	-32.91	71.52	40	-1.39	-5.8			Pass
2	46.46	39.96	35.6	-29.39	69.35	40	-0.04	-4.4			Pass
3	83.24	33.56	30.1	-34.51	68.07	40	-6.44	-9.9			Pass
4	116.16	40.72	35.9	-31.62	72.34	40	0.72	-4.1			Pass
5	131.65	33.74	29.6	-34.16	67.9	40	-6.26	-10.4			Pass
6	257.50	31.94	28.4	-28.57	60.51	47	-15.06	-18.6			Pass

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Vertical
Tester: CSL	Model: YDC3320H	Mode: FULL LOAD
Test Time: 2014/1/17 10:17	Temperature: 20	Humidity: 53
Power: AC 380V/50Hz	Test Distance: 10M	EUT: Uninterruptible Power supply
Note: BAT MODE		

## 2. Chart




## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Limit1	Margin Peak	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB (uV/m)	dB (uV/m)	dB	dB (uV)	dB (uV/m)	dB	dB	Degree	cm	
1	32.90	40.63	36.2	-32.71	73.37	40	0.63	-3.8			Pass
2	52.27	35.79	31.7	-29.79	65.59	40	-4.21	-8.3			Pass
3	96.80	39.05	35.7	-31.9	70.95	40	-0.95	-4.3			Pass
4	149.07	36.25	32.9	-35.29	71.54	40	-3.75	-7.1			Pass
5	195.54	33.55	30.6	-31.59	65.14	40	-6.45	-9.4			Pass
6	253.62	31.6	28.4	-29.86	61.46	47	-15.4	-18.6			Pass

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Horizontal
Tester: CSL	Model: YDC3340H	Mode: FULL LOAD
Test Time:2014/8/22 10:19	Temperature:20	Humidity:53
Power:AC 380V/50Hz	Test Distance:10M	EUT:Uninterruptible Power supply
Note:LINE MODE		

## 2. Chart




## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Linit1	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB (uV/m)	dB (uV/m)	dB	dB (uV)	dB (uV/m)	dB	Degree	cm	
1	31.45	36.89	34.2	-33.16	67.36	40	-5.8			Pass
2	108.98	30.21	28.6	-31.11	59.71	40	-11.4			Pass
3	148.71	35.55	32.1	-34.71	66.81	40	-7.9			Pass
4	239.80	27.45	24.3	-29.9	54.2	47	-22.7			Pass
5	280.49	29.83	26.5	-28.55	55.05	47	-20.5			Pass
6	297.94	26.44	22.5	-28.02	50.52	47	-24.5			Pass

## 1. Settings

Start: 30MHz	Step: 1GHz	
EBW: 100KHz	VBW: 300KHz	Ref: 100
RFAtt: 10	PreAmp: False	Polarization: Vertical
Tester: CSL	Model: YDC3340H	Mode: FULL LOAD
Test Time:2014/8/22 10:19	Temperature:20	Humidity:53
Power:AC 380V/50Hz	Test Distance:10M	EUT:Uninterruptible Power supply
Note:LINE MODE		

## 2. Chart




## 3. Result

No	Frequency	QP	Correct factor	Reading level	Limit1	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB (uV/m)	dB	dB (uV)	dB (uV/m)	dB	Degree	cm	
1	35.33	35.2	-32.12	67.32	40	-4.8			Pass
2	64.40	30	-31.29	61.29	40	-10			Pass
3	86.69	29.6	-33.62	63.22	40	-10.4			Pass
4	118.67	28.5	-32.12	60.62	40	-11.5			Pass
5	144.83	28.9	-34.38	63.28	40	-11.1			Pass
6	188.44	31.2	-31.22	62.42	40	-8.8			Pass

## 1. Settings

Start: 30MHz	Stop: 1GHz	
RBW: 100KHz	VBW: 300KHz	Ref: 100
RFAAtt: 10	PreAmp: False	Polarization: Horizontal
Tester: CSL	Model: YDC3340H	Mode: FULL LOAD
Test Time:2014/8/22 10:26	Temperature:20	Humidity:53
Power:AC 380V/50Hz	Test Distance:10M	EUT:Uninterruptible Power supply
Note:BAT MODE		

## 2. Chart



## 3. Result

No	Frequency	Peak	QP	Correct factor	Reading level	Limit1	Margin Peak	Margin QP	Table Degree	Antenna Height	Result
	MHz	dB(uV/m)	dB(uV/m)	dB	dB(uV)	dB(uV/m)	dB	dB	Degree	cm	
1	35.33	30.2	26.3	-32.34	58.64	40	-9.8	-13.7			Pass
2	72.15	32.95	30.2	-34.37	64.57	40	-7.05	-9.8			Pass
3	112.85	36.14	33.5	-31.62	65.12	40	-3.86	-6.5			Pass
4	145.80	32.24	29.5	-34.81	64.31	40	-7.76	-10.5			Pass
5	199.10	36.4	32.1	-30.97	63.07	40	-3.6	-7.9			Pass
6	210.72	37.61	34.1	-31.05	65.15	40	-2.39	-5.9			Pass



中国认可  
国际互认  
检测  
TESTING  
CNAS L2291

Standards EN62040-2: 2006 and IEC 62040-2:2005

## TEST REPORT

For

SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.

Uninterruptible power systems

Model Number: YDC3310S, YDC3310H, YDC3315S, YDC3315H,  
YDC3320S, YDC3320H, YDC3330S, YDC3330H,  
YDC3340H

Battery bank: YDC-BT battery bank series

Prepared for : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY  
CO., LTD.  
Address : 4/F, No.1 Bldg, Software Park, Keji C. Rd. 2nd,  
Hi-Tech Industrial Zone, Shenzhen 518057, P.R.China  
  
Prepared by : SHENZHEN EMTEK CO., LTD.  
Address : Bldg 69, Majialong Industry Zone,  
Nanshan District, Shenzhen, Guangdong, China

Tel: (0755) 26954280  
Fax: (0755) 26954282

Report Number : ES160322007E  
Date of Test : January 09, 2014 to January 21, 2014  
Date of Report : March 24, 2016

## TABLE OF CONTENT

Description	Page
<b>1. SUMMARY OF TEST RESULT.....</b>	<b>7</b>
<b>2. GENERAL INFORMATION.....</b>	<b>8</b>
2.1. Description of Device (EUT).....	8
2.2. Description of Support Device.....	9
2.3. Description of Test Facility.....	10
2.4. Measurement Uncertainty.....	10
<b>3. MEASURING DEVICE AND TEST EQUIPMENT.....</b>	<b>11</b>
3.1. For Conducted Emission Measurement.....	11
3.2. For Radiated Emission Measurement.....	11
3.3. For Harmonic Current / Flicker Measurement.....	12
3.4. For Electrostatic Discharge Immunity Test.....	12
3.5. For RF Strength Susceptibility Test.....	12
3.6. For Electrical Fast Transient/Burst Immunity Test.....	12
3.7. For Surge Immunity Test.....	13
3.8. For Injected Current Susceptibility Test.....	13
3.9. For Magnetic Field Immunity Test.....	13
3.10. For Voltage Dips and Interruptions Test.....	13
3.11. Low Frequency Signals Test.....	13
<b>4. CONDUCTED EMISSION MEASUREMENT.....</b>	<b>14</b>
4.1. Block Diagram of Test Setup.....	14
4.2. Measuring Standard.....	14
4.3. EUT Configuration on Measurement.....	14
4.4. Operating Condition of EUT.....	14
4.5. Test Procedure.....	15
4.6. Measuring Results.....	15
<b>5. RADIATED EMISSION MEASUREMENT.....</b>	<b>32</b>
5.1. Block Diagram of Test.....	32
5.2. Measuring Standard.....	32
5.3. Radiated Emission Limits.....	33
5.4. EUT Configuration on Test.....	33
5.5. Operating Condition of EUT.....	33
5.6. Test Procedure.....	33
5.7. Measuring Results.....	33
<b>6. HARMONIC CURRENT EMISSION MEASUREMENT.....</b>	<b>42</b>
6.1. Block Diagram of Test Setup.....	42
6.2. Measuring Standard.....	42
6.3. Operation Condition of EUT.....	42
6.4. Measuring Results.....	42
<b>7. VOLTAGE FLUCTUATION AND FLICKER MEASUREMENT.....</b>	<b>62</b>
7.1. Block Diagram of Test Setup.....	62
7.2. Measuring Standard.....	62
7.3. Operation Condition of EUT.....	62
7.4. Measuring Results.....	62
<b>8. IMMUNITY PERFORMANCE CRITERIA DESCRIPTION.....</b>	<b>71</b>
<b>9. ELECTROSTATIC DISCHARGE IMMUNITY TEST.....</b>	<b>73</b>
9.1. Block Diagram of Test Setup.....	73

9.2. Test Standard.....	73
9.3. Severity Levels and Performance Criterion.....	73
9.4. EUT Configuration.....	74
9.5. Operating Condition of EUT.....	74
9.6. Test Procedure.....	74
9.7. Test Results.....	74
<b>10. RF FIELD STRENGTH SUSCEPTIBILITY TEST.....</b>	<b>77</b>
10.1. Block Diagram of Test.....	77
<b>Control Room.....</b>	<b>77</b>
10.2. Test Standard.....	77
10.3. Severity Levels and Performance Criterion.....	77
10.4. EUT Configuration on Test.....	78
10.5. Operating Condition of EUT.....	78
10.6. Test Procedure.....	78
10.7. Test Results.....	78
<b>11. ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST.....</b>	<b>81</b>
11.1. Block Diagram of Test Setup.....	81
11.2. Test Standard.....	81
11.3. Severity Levels and Performance Criterion.....	81
11.4. EUT Configuration.....	82
11.5. Operating Condition of EUT.....	82
11.6. Test Procedure.....	82
11.7. Test Result.....	82
<b>12. SURGE IMMUNITY TEST.....</b>	<b>85</b>
12.1. Block Diagram of Test Setup.....	85
12.2. Test Standard.....	85
12.3. Severity Levels and Performance Criterion.....	85
12.4. EUT Configuration.....	86
12.5. Operating Condition of EUT.....	86
12.6. Test Procedure.....	86
12.7. Test Result.....	86
<b>13. INJECTED CURRENTS SUSCEPTIBILITY TEST.....</b>	<b>89</b>
13.1. Block Diagram of Test Setup.....	89
13.2. Test Standard.....	89
13.3. Severity Levels and Performance Criterion.....	89
13.4. EUT Configuration.....	90
13.5. Operating Condition of EUT.....	90
13.6. Test Procedure.....	90
13.7. Test Results.....	90
<b>14. MAGNETIC FIELD SUSCEPTIBILITY TEST.....</b>	<b>93</b>
14.1. Block Diagram of Test.....	93
14.2. Test Standard.....	93
14.3. Severity Levels and Performance Criterion.....	93
14.4. EUT Configuration on Test.....	94
14.5. Test Procedure.....	94
14.6. Test Results.....	94
<b>15. VOLTAGE DIPS AND INTERRUPTIONS TEST.....</b>	<b>97</b>
15.1. Block Diagram of Test Setup.....	97
15.2. Test Standard.....	97
15.3. Severity Levels and Performance Criterion.....	97
15.4. EUT Configuration.....	98
15.5. Operating Condition of EUT.....	98
15.6. Test Procedure.....	98
15.7. Test Result.....	98

<b>16. LOW FREQUENCY SIGNALS TEST.....</b>	<b>101</b>
16.1. Block Diagram of Test Setup.....	101
16.2. Test Standard.....	101
16.3. Operating Condition of EUT.....	101
16.4. Test Results.....	101
<b>17. TEST PHOTOGRAPH.....</b>	<b>104</b>
17.1. Photos of Conducted Emission Measurement.....	104
17.2. Photo of Radiation Emission Measurement.....	106
17.3. Photo of Harmonic / Flicker Measurement.....	108
17.4. Photo of Electrostatic Discharge Test.....	109
17.5. Photo of RF Field Strength susceptibility Test.....	110
17.6. Photos of Electrical Fast Transient/Burst Test.....	111
17.7. Photo of Surge Test.....	112
17.8. Photo of Injected Currents Susceptibility Test.....	113
17.9. Photo of Magnetic Field Immunity Test.....	114
17.10. Photo of Voltage dips and interruption Test.....	115
17.11. Photo of Low Frequency Signals Test.....	116

APPENDIX (Photos of EUT) (16 Pages)

## TEST REPORT VERIFICATION

Applicant : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.  
Manufacturer : SHENZHEN KSTAR SCIENCE AND TECHNOLOGY CO., LTD.  
EUT : Uninterruptible power systems  
Trademark : **KSTAR**  
Model Number : YDC3310S, YDC3310H, YDC3315S, YDC3315H, YDC3320S, YDC3320H,  
YDC3330S, YDC3330H, YDC3340H  
Power Supply : Please refer to page 8

### Measurement Procedure Used:

EN62040-2: 2006, IEC 62040-2:2005  
EN 61000-3-12: 2011  
EN 61000-3-11: 2000  
(IEC 61000-4-2:2008, IEC 61000-4-3:2006+A1:2007+A2:2010, IEC 61000-4-4:2012,  
IEC 61000-4-5:2014, IEC 61000-4-6:2013, IEC 61000-4-8:2009, IEC 61000-4-11:2004,  
IEC 61000-2-2:2002)

The device described above is tested by SHENZHEN EMTEK CO., LTD. to determine the maximum emission levels emanating from the device and the severe levels of the device can endure and its performance criterion. The measurement results are contained in this test report and SHENZHEN EMTEK CO., LTD. is assumed full of responsibility for the accuracy and completeness of these measurements. Also, this report shows that the EUT (Equipment Under Test) is technically compliant with the EN 62040-2 requirements.

This report applies to above tested sample only and shall not be reproduced in part without written approval of SHENZHEN EMTEK CO., LTD.

Date of Test : January 09, 2014 to January 21, 2014

Prepared by : 

Vern Fan/Editor

Reviewer : 

Jessie Hu/Supervisor

Approved & Authorized Signer : 

Lisa Wang/Manager

## Modified History

Rev.	Summary	Date of Rev.	Report No.
V1.0	Original Report	2016-03-24	ES160322007E

## 1. SUMMARY OF TEST RESULT

<b>EMISSION</b>			
Description of test item	Standard	Limits	Results
Conducted disturbance at mains terminals	EN62040-2: 2006	C2	Pass
Radiated Disturbance	EN62040-2: 2006	C2	Pass
Harmonic Current Emissions	EN 61000-3-12: 2011	Class A	Pass
Voltage Fluctuation and Flicker	EN 61000-3-11: 2000	Section 5	Pass
<b>Immunity</b>			
Description of test item	Basic Standard	Performance Criteria	Results
Electrostatic Discharge (ESD)	IEC 61000-4-2:2008	B	Pass
Radio-frequency, Continuous radiated disturbance	IEC 61000-4-3:2006+A1:2007+A2:2010	A	Pass
EFT/B Immunity	IEC 61000-4-4:2012	B	Pass
Surge Immunity	IEC 61000-4-5:2014	B	Pass
Conducted RF Immunity	IEC 61000-4-6:2013	A	Pass
Power frequency magnetic field	IEC 61000-4-8:2009	A	Pass
Voltage dips and Voltage interruptions	IEC 61000-4-11:2004	B	Pass
Low Frequency signals	IEC 61000-2-2:2002	A	Pass
Note: /			